



2024 Landscape Inspector Guidelines

Development
Inspections

City of Edmonton

Edmonton

TABLE OF CONTENTS

PART 1: GENERAL	8
1. INTRODUCTION	8
2. DEFINITIONS & TERMS	8
3. GENERAL ROLES AND RESPONSIBILITIES	15
3.1. City Of Edmonton Landscape Development Inspector.....	15
3.2. Consultant.....	16
3.3. Developer.....	16
3.4. Contractor.....	16
4. CODE OF CONDUCT AND RESPECTFUL WORKPLACE	17
5. SAFETY	17
5.1. Personal Safety.....	18
5.2. Field Level Hazard Assessment.....	18
6. SCOPE OF WORK	18
7. ANNUAL COLOUR TREE STAKES	20
8. QUADRANT INSPECTORS MAP AND CITY WEBPAGE	21
PART 2: MUNICIPAL IMPROVEMENT CONSTRUCTION	22
9. ROLES AND RESPONSIBILITIES	22
9.1. Landscape Development Inspector.....	22
9.2. Developer/Consultant.....	23
9.3. Contractor.....	23
10. PRE-CONSTRUCTION	24
11. SOIL TESTING	24
11.1. Roles And Responsibilities.....	24
11.1.1.1. Landscape Development Inspector.....	24
11.1.1.2. Developer / Consultant.....	25
11.1.1.3. Contractor.....	25
11.2. Soil Testing Procedure.....	25
12. AUDIT INSPECTIONS & MAJOR MILESTONES	26
12.1. Audit Inspection Procedures.....	26
12.1.1.1. Audit Inspection Timelines.....	27
12.2 Major Milestones.....	28
12.2.1 Tree Trench Audit.....	31
12.2.2 Root Barrier Installation.....	32
12.2.3 Natural / Existing Landscape Features.....	33
12.2.4 Soil Cells.....	33
13. IN-FIELD DESIGN CHANGE REQUEST	33
PART 3: INSPECTIONS AND CERTIFICATIONS	35
14. SERVICING AGREEMENT	35
14.1. Roles And Responsibilities.....	35

2024 Landscape Inspector Guidelines

14.1.1. Landscape Development Inspector.....	35
14.1.2. Developer/Consultant.....	36
14.1.3. Contractor.....	37
15. CONSTRUCTION COMPLETION CERTIFICATE (CCC).....	37
15.1. CCC Inspection Season.....	37
15.2. Preliminary CCC Inspection.....	38
15.3. Consultant Requirements Prior To CCC Application.....	38
15.4. CCC Inspection Application.....	39
15.5. CCC Inspection.....	42
15.6. CCC Inspection Appeal Process.....	43
15.7. CCC Documentation Requirements.....	43
15.7.1 CCC Only Documentation Package.....	45
15.8. CCC Process Flow Chart.....	45
16. LANDSCAPE INSPECTION DEFICIENCIES.....	47
16.1. Sod, Shrubs And General.....	47
16.2. Tree Inspection Deficiencies.....	48
16.2.1. Pests and Disease.....	48
16.2.2. Tree Vigor.....	49
16.2.3. Tree Structure and Form.....	50
16.2.4. Examples of Some Common Tree Deficiencies.....	52
17. WARRANTY PERIOD MAINTENANCE.....	55
18. FINAL ACCEPTANCE CERTIFICATE (FAC).....	56
18.1. FAC Inspection Season.....	56
18.2. Preliminary FAC Inspection.....	57
18.2.1. Examples of Sites NOT Ready to Request FAC Inspections.....	58
18.3. Consultant Requirements Prior To FAC Application.....	60
18.4. FAC Inspection Application.....	60
18.5. FAC Inspection.....	62
18.6. FAC Inspection Appeal Process.....	63
18.7. Extending Establishment Periods.....	64
18.8. FAC Documentation Requirements.....	65
18.9. Common Accuracy Items In As-Built Drawings.....	66
18.10. FAC Process Flowchart.....	67
18.11 LANDSCAPE CCC AS-BUILT DRAWING SUBMISSION PROCESS UPDATE.....	69
18.11.2 Key Changes At A Glance.....	69
18.11.3 PHASE 1: Initial CCC Submission / Inspection / Result.....	69
18.11.4 PHASE 2: CCC As-Built Documentation.....	70
18.11.4.1 Introduction of New Requirements.....	70
18.11.4.2 Spatial Tolerance Requirements for Asset Placement:.....	70
18.11.4.3 Documentation Requirements:.....	70
18.11.5 FAC Submissions & Inspection & Result (Unchanged):.....	72
18.11.5.1 Department Review Phase Existing Process (Unchanged):.....	73
18.11.5.2 *New Requirement*:.....	73
PART 4: SUPPLEMENTARY MUNICIPAL IMPROVEMENT INFORMATION.....	74

2024 Landscape Inspector Guidelines

19. FAC TREE BUYOUT PROGRAM.....	74
19.1. FAC Tree Buyout Eligibility.....	74
19.2. Roles And Responsibilities.....	75
19.2.1. Landscape Development Inspector.....	75
19.2.2. Consultant.....	75
19.2.3. Developer.....	75
19.2.4. Contractor.....	76
19.2.5. Landscape Development Inspector Supervisor.....	76
19.3. FAC Tree Buyout Application.....	76
19.3.1. Phase 1 of Tree Buyout Application.....	76
19.3.2. Phase 2 of Tree Buyout Application.....	76
19.3.3. Phase 3 of Tree Buyout Application.....	78
20. AMENITIES INSPECTIONS.....	79
20.1 Roles And Responsibilities.....	79
20.1.1. Infrastructure Maintenance (IM) Inspector.....	79
20.1.2. Landscape Development Inspector.....	79
20.1.3. Transportation Development Inspector.....	79
20.1.4. Developer/Consultant.....	80
20.1.5 Contractor.....	80
20.2. Pre-Construction Meeting.....	80
20.3. Hardstop Inspection Application.....	80
20.3.1. Hardstop Inspection Stages.....	80
20.4. Landscape Amenities CCC Inspection.....	81
20.5. Landscape Amenities Warranty Period.....	83
20.6. Landscape Amenities FAC Inspection.....	83
21. FENCING INSPECTIONS.....	84
21.1. Roles And Responsibilities.....	84
21.1.1. Landscape Development Inspector.....	84
21.1.2. Transportation Development Inspector.....	84
21.1.3. Developer/Consultant.....	85
21.1.4. Contractor.....	85
21.2. Fencing CCC Inspection Application.....	85
21.3. Application For Photo CCC Inspection.....	86
21.4. Eligibility For Photo Inspections.....	86
21.5. On Site Fence Inspections.....	87
21.6. Fencing FAC Inspection.....	90
22. PLAYGROUND INSPECTIONS.....	91
22.1. Roles And Responsibilities.....	91
22.1.1. Landscape Development Inspector.....	91
22.1.2. Infrastructure Maintenance (IM) Inspector.....	91
22.1.3. Transportation Development Inspector.....	91
22.1.4. Developer/Consultant.....	92
22.2. Playground Pre-Construction Meeting.....	92
22.3. Playground Construction Hardstop Inspection Requirements.....	92

2024 Landscape Inspector Guidelines

22.3.1. Hardstop Inspections Application.....	93
22.3.2. Hardstop Inspection Stages.....	93
22.4. Playground CCC Inspection Request Requirements.....	94
22.5. Playground CCC Inspection Application.....	95
22.6. Playground CCC Inspection.....	95
22.7. Playground Warranty Period.....	97
22.8. Playground FAC Inspection.....	97
23. SHARED PARK SITE INSPECTIONS.....	98
23.1. Roles And Responsibilities.....	98
23.1.1. Developer/Consultant.....	98
23.1.2. City's Development Inspections Unit.....	98
23.1.3. Shared Park Development Group.....	99
23.1.4. City Operations.....	99
23.2. Shared Park CCC Application.....	99
23.3. Shared Park CCC Inspection Request Requirements.....	100
23.4. Shared Park CCC Certificate Requirements.....	100
23.5. Appeal Process.....	100
24. NATURAL AREAS INSPECTIONS.....	101
24.1. Intent Of Inspection For Natural Sites.....	101
24.2. Pre-Construction Inspection Of Natural Area.....	102
24.3. Audit Inspections.....	102
24.4. Natural Areas CCC / FAC Inspections.....	103
25. LOW IMPACT DEVELOPMENT (LID) INSPECTIONS.....	106
LANDSCAPE CHECKLIST AT CCC.....	120
LANDSCAPE CHECKLIST AT FAC.....	124

APPENDICES**[APPENDIX A: CODE OF CONDUCT AND RESPECTFUL WORKPLACE](#)****[APPENDIX B: LANDSCAPE INSPECTIONS HAZARD ASSESSMENT](#)****[APPENDIX C: LANDSCAPE INSPECTION CHECKLIST](#)****[APPENDIX D: CCC/FAC LANDSCAPE INSPECTION REQUEST FORMS](#)****[APPENDIX E: FENCING CCC INSPECTION PHOTO SUBMISSION](#)****[APPENDIX F: NATURAL AREA INSPECTION CHECKLIST](#)****[APPENDIX G: EXAMPLE CONSULTANT PRE-INSPECTION REPORT & \(OPTIONAL\) CHECKLIST](#)****[APPENDIX H: EXAMPLE HIGHLIGHTED MAP FOR INSPECTION](#)****[APPENDIX I: EXAMPLE OF TREE BUYOUT SUBMISSION](#)****[APPENDIX J: EXAMPLE TREE BUYOUT DEFICIENCY REPORT & COST ESTIMATE SHEET](#)****[APPENDIX K: EXAMPLE AS-BUILT PLANS](#)****[APPENDIX L: EXAMPLE LANDSCAPE PLAN INDICATING YEARS ALL TREES PLANTED](#)****[APPENDIX M: SOIL SAMPLE MAP](#)****[APPENDIX N: WEBSITE LINKS AND REFERENCE DOCUMENTS](#)****[APPENDIX O: PLAYGROUND CCC/FAC CITY FORM](#)**

Terms of Use:

The City of Edmonton recognizes the 2024 Landscape Inspectors Guidelines as accurate and comprehensive, and approves its use within the City.

We do not intend these guidelines to replace any of the City Design and Construction Standards, nor any bylaws and legislations - the latest editions of these documents will continue to govern.

If any user has concerns about the accuracy or intent of these guidelines, they can seek clarification from the Landscape Development Inspector Supervisor.

Documents Revision Notice:

Please note that the current edition of the document has been updated with minor revisions to ensure accuracy and clarity. The changes include routine updates and editorial refinements. Each modification has been carefully reviewed to maintain the integrity and consistency of the information presented. The revisions are as follows:

Replacements: Minor corrections in phrasing and terminology to reflect the latest industry standards.

Insertions: Additional information included to address previously underrepresented areas.

Deletions: Removal of outdated or redundant text that does not alter the document's core content.

Styling: Updates to the document's format and design to improve readability and navigation.

Annotations: Editorial notes and comments for clarity.

Change from 2023 edition to 2024 edition summary.

Total Changes	Content	Styling and Annotations
1941	730 Replacements	100 Styling
	643 Insertions	
	211 Deletions	

The most important Revision Summary items

- | | |
|--|----------------------|
| • Improve Overall Navigation | MAJOR UPDATES |
| • Annual Colour Tree stakes | MINOR UPDATES |
| • Quadrant Inspectors map and contact | MAJOR UPDATES |
| • Audit Inspections & Major Milestones | MINOR UPDATES |
| • In-Field Design Change Request | NEW ITEM |
| • Tree Inspection Deficiencies | MINOR UPDATES |
| • Consultant Pre-Inspection Report & (Optional) Checklist | MAJOR UPDATES |
| • Landscape As-Built Drawing Submission at CCC | NEW ITEM |
| • FAC Tree Buyout Program | MINOR UPDATES |
| • Fencing Inspections | MINOR UPDATES |

PART 1: GENERAL

1. INTRODUCTION

The Development Inspections Landscape Inspector Guidelines (herein referred to as Guidelines) provides comprehensive guidance for inspecting private development projects in the City of Edmonton. **Its primary aim is to improve the consistency, transparency, and accountability between the City and the private development community, including Developers, Consultants, and Contractors.**

This document is useful for inspectors at all levels of experience, outlining their duties and expectations, as well as providing examples of standardized forms, inspection checklists, and reference tables. Adherence to the procedures outlined in this document will ensure the standardized administration of Servicing Agreements, leading to a better experience for all parties involved. It is important to note that the procedures for obtaining a Construction Completion Certificate (CCC) and Final Acceptance Certificate (FAC) are based on the latest version of the Servicing Agreement and may differ from previous versions.

2. DEFINITIONS & TERMS

The following definitions and terms that are used in the Guidelines are defined as follows:

AAALA: Alberta Association of Landscape Architects.

Agreement or Servicing Agreement: Refers to a contractual agreement between one or more Developers and the City of Edmonton that specifies the contractual obligations and the terms and conditions for the construction and warranty of Municipal Improvements necessary to service lands approved for development and includes technical set of landscape drawings that communicate the design and construction, as intended by a Landscape Architect. This will include the supplementation of details, elevations, grading, and any other detailed representation of the asset.

APEGA: Association of Professional Engineers and Geoscientists of Alberta.

As-Built Drawings: As-Built drawings show how the site was built versus the way it was originally designed. At the completion of the construction and installation of an improvement, the as-built drawings describe what was actually built. This must be a scaled drawing that documents the changes from the approved drawings submitted by the

2024 Landscape Inspector Guidelines

Landscape Architect. This submission must be stamped, signed, and dated with the most recent submission referencing “Issued for As Built”. This must reflect the as-is conditions at the time of signing.

Asset Cost Form (ACF): Refers to a record of the cost of an asset and may include the gross amount to acquire, construct, develop or improve a tangible capital asset at the date of contribution. This includes installing the asset at the location and in the condition necessary for its intended use.

Audit Inspection: Unannounced and unscheduled site visits conducted by the Landscape Development Inspector to ensure that the site is being built in accordance with City Standards. These inspections can encompass, among others, physical examinations or site visits, assessments from vehicle drive-bys, conversations with the Contractor/Consultant, taking measurements and/or conducting sampling and testing, as required.

Balled & Burlap: Trees established in the ground that have been harvested by digging with a soil ball so that the soil within the ball remains undisturbed. Trees harvested by this method will have been field grown for at least 3 years prior to harvesting.

Business Day: Refers to a regular workday and typically excludes weekends and statutory holidays.

City: Refers to The City of Edmonton (COE) as a corporate body or a City-owned corporation.

Construction Completion Certificate (CCC): Refers to a document signed and sealed by a Professional Engineer or PM (as applicable); a Professional Technologist within their professionally permitted scope of work; or, a Landscape Architect, certifying that a Municipal Improvement has been constructed in accordance with the applicable approved Engineering Drawings and the terms of the corresponding Servicing Agreement, and is operational, functional, and safe.

Consultant: Refers to the Professional Engineer or Professional Technologist responsible for the preparation of designs, reports, studies, Engineering Drawings and associated documents and for the execution and implementation of such designs, normally on behalf of a Developer. The Consultant must hold a valid Permit to Practice, as defined by the Association of Professional Engineers and Geoscientists of Alberta (APEGA) and be registered as a Professional Engineer in good standing with APEGA, or be registered as a Professional Technologist within the Province of Alberta and be in good standing with the Association of Science and Engineering Technology (ASET) Professionals of Alberta, and be

2024 Landscape Inspector Guidelines

operating within the defined scope of practice for which the Professional Technologist is professionally permitted. For any landscape designs, reports, studies, drawings, or other associated documents, the Consultant must be a member in good standing of the Alberta Association of Landscape Architects (AALA).

Contractor: Refers to a person, partnership, company, or group of persons who work for the Developer and undertake all or part of the work.

Days: Refers to the number of business days, unless noted otherwise.

Deficiency: Refers to any fault or defect that impedes functionality, poses a safety hazard, does not meet City specifications and standards, or deviates from the approved drawing, as outlined in the Guidelines.

Deficiency Inspection Report (Deficiency Report / Deficiency Plan): Refers to a site plan that clearly labels the locations of all identified deficiencies from a CCC or FAC Inspection. This Deficiency Plan will be used by the Consultant to direct the Contractor on how to correct the deficiencies in order to obtain an approved CCC or FAC.

Department Review: All aspects of the certification approval process which includes the Landscape Development Inspector reviewing uploaded documents on ePlan once an inspection has been approved on eServices.

Design and Construction Standards (City Standards): Refers to all specifications contained in the City of Edmonton Design and Construction Standards, Volume 5: Landscaping. All projects that are initiated into circulation as of April 1, 2021 shall follow the 2021 edition or later. Change with circulation as of April 1, 2022, shall follow the 2022 edition or later.

Developer: Refers to the proponent developing land, or the Owner as defined in the Servicing Agreement. Requirements of the Developer, as stated in the Design and Construction Standards, may, where appropriate, be deferred to a Consultant, Contractor or other agent acting on the Developer's behalf.

Document Package: Refers to the supporting documentation required to support the CCC/FAC certification. This is submitted to ePlan for review and must be approved by COE prior to certification approval.

Engineer: Refers to the Engineer allowed by the City or utility agency to enforce the Design and Construction Standards, and review and approve design submissions, reports, proposals, and Engineering Drawings. In addition, when applicable, the Engineer refers to

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

the authority in the Servicing Agreement to enforce conditions of the Servicing Agreement in relation to servicing proposals and designs of Municipal Improvements under the terms of a Servicing Agreement between the City and a Developer(s). The Engineer must hold a valid permit to practice within the Province of Alberta and be registered as a Professional Engineer in good standing with APEGA. The Engineer also includes individuals authorized by the Project Engineer to perform any engineering functions on their behalf.

Engineering Drawings: Refers to the plans that set out the scope and detail of the Municipal Improvements to be provided by the Developer under the terms of the Servicing Agreement and shall refer to or include, where applicable, landscape drawings. The Engineering Drawings must be assembled under the cover of a Consultant eligible to practice engineering within the Province of Alberta and registered with APEGA.

Environmental Reserve (ER): Refers to land that is set aside specifically for the protection and preservation of the natural environment. These areas may include parks, wetlands, woodlands, and other ecosystems that are important for the maintenance of biological diversity and ecological health.

ePlan: Refers to an online tool that Consultants use for the electronic application of inspection requests and review of Engineering Drawings.

eServices: Refers to an online tool that Developers and Consultants use to submit inspection requests for Municipal Improvements and obtain development certificates.

EPCOR: Refers to the utility company that provides services including electricity, natural gas, and water.

Final Acceptance Certificate (FAC): Refers to a document signed and sealed by either a Professional Engineer or PM (as applicable); a Professional Technologist within their professionally permitted scope of work; or, a Landscape Architect, certifying that a Municipal Improvement/asset has been constructed and maintained in accordance with the applicable approved Engineering Drawings and meets the terms of the corresponding Servicing Agreement. It also signifies that the Developer's obligation to maintain the Municipal Improvement will be transferred to the City. It confirms that the improvement has been constructed and maintained in accordance with the City of Edmonton Design and Construction Standards, meets the terms of the Servicing Agreement, and is constructed as per the approved engineering drawings. It confirms that the asset is operational, functional and safe and that it does not contain any construction deficiencies, with the exception of normal wear and tear.

2024 Landscape Inspector Guidelines

FOIP: Freedom of Information and Protection of Privacy.

Hardstop Inspection : Required inspections conducted at certain points of the construction process.

Inspection: Refers to a scheduled site visit to conduct a visual and physical review of various aspects of the landscaping assets and identify any deficiencies that require corrective action. It must be requested through eServices and conducted by or with the City's Landscape Development Inspector.

Landscape Development Inspector: Refers to an individual specifically delegated by the City as having the authority to conduct an Audit Inspection and approve CCC and FAC Inspections, including Tree Buyouts.

Landscape Development Supervisor: Refers to the individual who oversees the Landscape Inspections Team within the Development Inspections Unit of the Development Services Branch within the Urban Planning and Economy (UPE) Department at the City of Edmonton.

Landscape In-Field Design Change Request: Deviation from the approved drawings necessitated by conditions in the field that occur prior to construction, during construction, or during the maintenance period after the drawings have been approved. Landscape In-Field Designs Change Request will require application and approval. These changes will negate the need for a redline but all change request must not affect other reviewing departments.

Low Impact Development (LID): Refers to the land development and stormwater management approach that works with nature to manage stormwater as close to the source as possible. LID focuses on maintaining and restoring the natural hydrological processes of a site.

Maintenance Logs: Refer to a listing of the maintenance tasks that have been performed on a specific site. As each site requires different levels of maintenance and service, it becomes important to generate, track, and review the list of completed action items on an ongoing basis. Maintenance Logs can be used to determine what level of care is still required, based on site conditions, to ensure a functional and viable asset. Maintenance Logs should correspond closely to the predetermined Maintenance Schedule but often, due to changing site conditions, variances will be found between the two documents.

2024 Landscape Inspector Guidelines

Maintenance Schedule: Refers to a list, or program, created by the Contractor with the aim of ensuring that proper care is given to a constructed site (based on City Standards). The schedule helps determine the number of times a Contractor will visit the site and the intervals between these visits. The Maintenance Schedule is also used to predetermine the type of appropriate maintenance for a given site and should be updated regularly, as part of a proactive approach, to reflect the current site conditions.

Milestone: Key hold points throughout the construction process. An audit or an inspection may be required prior to progressing to other related activities.

Municipal Improvement (or “Infrastructure”): Refers to both underground and surFACe structures including, but not necessarily limited to, water mains, sewer systems, storm drainage systems, roadways, walkways, park areas, shallow utilities, signage, retaining walls, fencing, and other improvements as required by the City, all of which shall become the property of the City to operate and maintain.

Municipal Reserve (MR): Refers to an area of land that is set aside for specific public purposes, as designated by the municipality. These lands may serve as protection for natural areas, wetlands, or wildlife habitats, or may be used for community FACilities, such as parks, schools, or utility infrastructure.

Naturalization: Refers to a type of habitat restoration; the deliberate reintroduction of species that are native to a given area or are well adapted to the climate circumstance; activities that are intended to improve and enhance the natural environment and reduce the required operational maintenance. The biodiversity and ecosystem function of a naturalized ecosystem is lower compared to a reference habitat but higher compared to a reclaimed ecosystem.

Open Space Asset: Refers to any future public land, infrastructure or FACilities that are designated for recreational or leisure use. This can include parks, playgrounds, sports fields, community gardens, and other similar areas that are intended for the enjoyment and use of the general public. Open Space Assets are typically owned and maintained by the City of Edmonton and are designed to provide safe and accessible spaces for residents to enjoy a range of outdoor activities.

Public Utility Lot (PUL): Refers to a titled lot that is intended to provide for infrastructure and utility FACilities, maintenance FACilities and public transportation use. They can be operated (individually or jointly) by the Federal, Provincial, and Municipal levels of government.

2024 Landscape Inspector Guidelines

Ready Site: Refers to a site that is deemed to be constructed and completed according to the approved Engineering Drawings. The site meets the City's Design and Construction Standards and poses no safety risk to those using the space. The site should be free of construction equipment, maintenance activity, vehicles, material stockpiles, or debris that may prevent access or impede the inspection.

Redline Drawings: Refer to changes to the Engineering Drawings that occur after the original approval of the Engineering Drawings. These changes must follow the City's standard process for Redline Drawings, as described in the City's Design and Construction Standards, Volume 1: General.

Right of Way (R.O.W): Refers to an agreement that grants an individual, company or municipality the right to use private property in some way.

Stormwater Management FACility (SWMF): Refers to stormwater ponds, including dry ponds, wet ponds, wetlands, and any combinations thereof (hybrid ponds). It is an integral part of a major storm drainage system that receives stormwater runoff from conveyance systems (ditches, drainage swales, roads and gutters, and storm sewers) and discharges to receiving waters such as wetlands, lakes, ponds, streams, and/or to downstream conveyance systems.

Tree Buyout: Refers to agreements made and funds received from development or capital projects for the buyout on Servicing Agreement or capital projects, upon agreement with the City Manager, to transfer site deficiencies to the City to achieve a Final Acceptance Certificate.

Tree Protection Policy: Refers to a set of [regulations and guidelines](#) designed to protect the urban forest and maintain the health and vitality of trees in the community. The policy outlines measures for protecting trees during development, construction, and other activities, as well as guidelines for planting and caring for trees on private and public lands.

Utility Encroachment: Refers to Refers to infrastructure such as power, gas, telecommunications, water lines and sewers that are installed within private lands

Warranty Period (Maintenance Period): Refers to the period of time that the Developer shall maintain the asset in accordance with the Servicing Agreement.

3. GENERAL ROLES AND RESPONSIBILITIES

Once a project is ready to start, certain key stakeholders should be involved. The responsibilities of each stakeholder are defined in the following subsections. Each party should be familiar with the Guidelines and should refer to them for submission of inspection applications and specific documentation required for CCC and FAC.

The roles and responsibilities of the City may be fulfilled by representatives from an applicable City department, EPCOR Water Services Inc. – Water Canada, EPCOR Water Services Inc. – Drainage Services, or EPCOR Distribution and Transmission Inc., as appropriate in each situation.

In addition, the roles and responsibilities of the Owners/Developers may be fulfilled by their employees, Consultants, Contractors or agents, as appropriate.

3.1. City Of Edmonton Landscape Development Inspector

The City of Edmonton Landscape Development Inspector's main task is to ensure that work is carried out and that Municipal Improvements are constructed in accordance with the City Design and Construction Standards and the approved Engineering Drawings. This objective is satisfied by conducting site visits to check construction progress, and offering guidance, as required. The Landscape Inspector's main responsibility is to observe, verify, record, and report any problems, issues, or non-compliance observed. They must report these to the Consultant or their representatives. The Landscape Development Inspector has no direct authority over private development construction, which is governed by the Servicing Agreement. They cannot direct or manage Contractors or their work beyond the Guidelines, the City's Design and Construction Standards, and the Servicing Agreement. Therefore, the Landscape Development Inspector cannot be held accountable for any non-compliance or necessary corrections. The best results are achieved through informed, cooperative, and collaborative efforts.

During the inspection process, the Landscape Development Inspector will track each site via an internal Google Form. This tool is used to record project activity, milestones, informal and CCC/FAC Inspections, and any related issues on an ongoing basis. Entries should be made at the Landscape Development Inspector's earliest convenience and with as much pertinent detail as practical. At the end of the year, the Landscape Development Supervisor

can share the statistical summary with the industry at the City's discretion and with Freedom of Information Protection (FOIP) protocols followed.

3.2. Consultant

The Consultant refers to the Professional Engineer or Professional Technologist responsible for the preparation of designs, reports, studies, landscape drawings, and associated related documents. They oversee and manage the construction and implementation of the approved Engineering Drawings on behalf of the Developer, including on-site project management and supervision. The Consultant must be registered as a Landscape Architect in good standing with the AALA and where required, have a valid Permit to Practice from APEGA.

3.3. Developer

The role of ensuring feasible implementation methods throughout the development process falls to the Consultant. They assign responsibilities to ensure that all Municipal Improvements are built according to the Servicing Agreement and sound engineering practices.

Clause 1.5.3 of the Design & Construction Standards Volume 1 (General Provisions for Developers) states that the Developer is responsible for ensuring that the Consultant provides all necessary equipment, tools, and labor for inspection, quality control, and administrative duties during construction. The City's role in inspecting the project is limited to monitoring and does not absolve the Developer of their responsibility for all aspects of the work. The Developer remains fully responsible for the quality control, coordination, and safety of the construction process.

3.4. Contractor

The companies engaged and directed by the Developer and/or Consultant to construct the improvements as per the approved Engineering Drawings package and align with the City's Design & Construction Standards. The Contractor may act as a representative for the Developer if declared accordingly.

4. CODE OF CONDUCT AND RESPECTFUL WORKPLACE

As a City Employee, the Landscape Development Inspector must comply with the City of Edmonton Code of Conduct Handbook and Guide (refer to [Appendix A](#)). Landscape Development Inspectors must read, understand, and comply with these regulations.

On-site, the Landscape Development Inspector is the liaison between the City and the Developer, and between the City and the general public. The Landscape Development Inspector must perform their duties in a courteous and respectful manner. A Landscape Development Inspector is a highly visible representative of the City and must remain above reproach in both conduct and appearance. They must be honest, reliable, and impartial.

The Landscape Development Inspector should maintain a positive and helpful attitude toward the project - this benefits all aspects of the work. When dealing with the Developer and/or Consultant, the Landscape Development Inspector should stay impartial and avoid conflicts of interest.

The Landscape Development Inspector should address any requests, questions or recommendations from the Developer and/or Consultant. If there is any uncertainty in what they are proposing, the Landscape Development Inspector should contact the Landscape Development Supervisor for direction.

The City of Edmonton is committed to creating and maintaining a vibrant, healthy, safe and respectful workplace for all employees. A respectful workplace is one that is free of harassment and discrimination, where all employees are treated fairly, diversity is acknowledged and valued and there is a culture of inclusion. Every employee has a shared responsibility to create and maintain a respectful workplace, where you can do your best work.

5. SAFETY

Safety regulations can reduce risk, but never eliminate it. A construction site is a dangerous place – think and act accordingly. Traffic and pedestrian safety is the responsibility of the Developer. The Landscape Development Inspector should ensure safe practices are being followed. All unsafe conditions and actions should be reported to the Contractor and/or Consultant. Compliance with the Occupational Health and Safety (OH&S) Act is mandatory. When on-site, the Landscape Development Inspector must follow the Prime Contractor's site safety protocol at all times.

[\(back to top\)](#)

5.1. Personal Safety

Personal safety is the individual responsibility of everyone on site. The following items should be considered at all times:

- Remain alert
- Ensure that you are visible
- Wear all applicable personal protective equipment (PPE) (safety helmet & footwear, high-visibility vest, etc.)
- Report all near misses as outlined in OH&S standards
- Landscape Development Inspectors Should be informed of machinery on site or areas with safety concerns prior to the start of the inspection.
- Ensure the area to be inspected is accessible, free of obstructions and not behind construction fencing.
- The Landscape Development Inspector has the right to postpone an inspection if the weather conditions are not suitable (ie. thunder or too cold/icy).

5.2. Field Level Hazard Assessment

- All possible hazards should be assessed and documented each day on the Landscape Development Inspector's Inspection Tracker (Ref: City Job hazard assessment- Job Position [Appendix B](#))
- Safety audits will be conducted throughout the City by Development Landscape Supervisor at a frequency of at least 12 random inspections per year.

6. SCOPE OF WORK

See Section 3.0 “Roles and Responsibilities” and Section 3.1 “Code of Conduct/Respectful Workplace” for details of general inspection expectations.

The Servicing Agreement and the approved Engineering Drawings agreed upon by the City and the Developer establish the minimum acceptable standards of work for each Municipal Improvement. The Landscape Development Inspector is responsible for thoroughly understanding the Standards, Servicing Agreement, and approved Engineering Drawings to ensure that all stakeholders comply with these requirements throughout the project. The

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

Landscape Development Inspector and the City of Edmonton may, at their discretion, decide to surpass the minimum specifications in certain situations where there is a risk to health and safety, or existing infrastructure or City-owned assets.

Unless the design specifications indicate a particular technique, the Contractor may choose any reasonable method to produce the desired end result. This method must be first approved by the City. If the Landscape Development Inspector believes that a particular method will result in an unacceptable product, they must provide notice to the Consultant using reasonable efforts.

According to the Design and Construction Standards, if the Developer wishes to apply methods which differ from a standard or specification in this document, or if these standards or specifications do not cover a subject of concern to a specific design, or if the Developer proposes to use materials not approved in this document, then the responsibility shall be on the Developer to justify the proposal or resolve the concern to the satisfaction of the City. The concern shall be the subject of a report that the Developer shall have prepared by a Landscape Architect or Professional Engineer and signed, sealed and submitted to the City for review.

The Landscape Development Inspector must be aware of what is in the Project's Servicing Agreement, the approved Engineering Drawings and the type of Municipal Improvement, and must notify the Developer or Developer representatives when the expectations are not being met. Note that the Landscape Development Inspector should work with the Developer, Consultants, and Contractors rather than against them. By referencing the City of Edmonton Design and Construction Standards fairly, the Developer will understand what is expected of them and achieve consistent outcomes.


The Landscape Development Inspector should not direct or perform any of the work. This impairs the Landscape Development Inspector's ability to inspect objectively.

7. ANNUAL COLOUR TREE STAKES

2023	Green
2024	Blue
2025	White
2026	Yellow
2027	Green

8. QUADRANT INSPECTORS MAP AND CITY WEBPAGE

Development Landscape Inspector City Webpage and Resources



Edmonton

URBAN PLANNING AND ECONOMY

2024 DEVELOPMENT INSPECTIONS - LANDSCAPE UNIT

7th Floor Edmonton Tower
1011 - 104 Avenue NW
Edmonton, Alberta
T5J 0L4

Director:
Mark Provost 780 720 4512

General Supervisor:
Annie Duong 780 442 0251

Senior Engineer:
Transportation Inspections
Trevor Spingell 780 496 7019

Senior Engineer:
Standards, Utilities & Arterial Road Coordination
Hazel Beldell 780 903 3322


Acting Program Supervisor:
Curtis Smithler curtis.smithler@edmonton.ca

Amendments Inspector:
Derek Chartrand derek.chartrand@edmonton.ca

Administrative Assistant:
Stefanie Groulx stefanie.groulx@edmonton.ca

NorthWest Inspector:	NorthEast Inspector:
Suzana Bodnar 780 721 0338	Leslie Revell 780 886 6465 Britton Austin 780 906 1025
SouthWest Inspector:	SouthEast Inspector:
Audrey Halko 780 901 1754	Stephanie Pike 780 909 1754 Megan Sankey 780 686 1871
City Wide - Landscape Unit Supervisor:	City Wide - Landscape Unit Supervisor:
Olivier LeTymewez-Dohal 780 554 8961	Olivier LeTymewez-Dohal 780 554 8961

Below is a link to the website (copy and paste):
<https://www.google.com/maps/@53.545885,-113.508185,12z/data=!4m2!3m1!1s0x53545885113508185:0x53545885113508185>



This map is Not To Scale

PART 2: MUNICIPAL IMPROVEMENT CONSTRUCTION

Please refer to Article 5 of the Servicing Agreement - Construction, Operation and Warranty of Municipal Improvements.

9. ROLES AND RESPONSIBILITIES

9.1. Landscape Development Inspector

Refer to the 2024 Servicing Agreement, Section 5.5.

- Completing inspections of the work is being performed in accordance with the approved Engineering Drawings, Specifications, applicable laws and regulations, and the City of Edmonton Design and Construction Standards.
- Conducting visual and physical inspections.
- Monitoring and advising on erosion and sedimentation control measures where it is out of the jurisdiction of EPCOR.
- Having representatives from other City Departments or Units assist with the Audit Inspections, as required.
- Keep detailed records of all inspections, tests, and observations, and maintain an accurate and up-to-date project file.
- Communicating any noted deficiencies to the appropriate party for correction.
- Ensuring that assets are in a state of the intended quality and function.
- Recommending alternatives if Audit Inspections reveal construction practices that are not up to the current standards.
- Recommending ongoing communication between the Consultant and the Landscape Development Inspector during this phase.

2024 Landscape Inspector Guidelines

- Ensuring that any noted major deficiencies can be addressed before the formal inspection.

9.2. Developer/Consultant

Refers to 2024 Servicing Agreement, Section 5.4 (Ongoing Obligation During Construction).

- Being aware of the progress of the site construction and directing the work as needed.
- Contact the Landscape Development Inspector for all Major Milestone Audit Inspections that are required via [the 2024 Landscape Development Intake Requests Form](#), within a minimum of 2 business days.
- Notifying the Landscape Development Inspector for any Audits, Milestones, and and Soil testing locations via [the 2024 Landscape Development Intake Requests Form](#) is crucial. Failure to do so may result in the asset being requested to be removed and replaced in the inspection report.
- Recommending ongoing communication between the Consultant and the Landscape Development Inspector during this phase to ensure the majority of major deficiencies can be addressed before the inspection.
- Referring to inspection requirements as per Section 18.0, Section 20.0 and Section 23.0 of this document for more details.
- Submitting Redline Drawings to the City for approval for any deviations from the approved Engineering Drawings, as deemed necessary by the City and in accordance with Volume 1 of the City's Design and Construction Standards prior to construction of affected infrastructure.
- Submit a Landscape In-Field Design Change request form that will address changes that occur prior to construction, during construction, or during the maintenance period after the drawings have been approved for approval prior to implementation.
- Collect and record as-built information for Municipal Improvements.

9.3. Contractor

- Building the Municipal Improvement according to the approved Engineering Drawings and the City's Design and Construction Standards.

2024 Landscape Inspector Guidelines

- Taking direction from the Consultant, as necessary, and/or if changes are required.
- Ensuring ongoing communication between the Contractor and the Consultant during this phase to ensure the site is constructed appropriately.
- Addressing major and minor deficiencies before inspections, where possible.

10. PRE-CONSTRUCTION

Prior to the start of any Municipal Improvements, the Developer or their representatives shall arrange for an on-site pre-construction meeting to take place with all relevant City Departments and EPCOR.

At least three business days prior to the Pre-Construction Meeting, the Developer or their representatives shall provide written notice to all relevant City Departments and EPCOR of their intention to start construction and provide copies of approved Engineering Drawings (digital and hard copies) to, and to the satisfaction of, all relevant City Departments.

In the event that the Landscaping Inspector can not attend the pre-construction meeting, the consultant can share the meeting minutes with the inspector.

11. SOIL TESTING

As identified in Volume 5: Landscaping of the City's Design and Construction Standards, **soil testing will be required for all drawings entered into circulation after April 1, 2021**. Please refer to Volume 5 for detailed information regarding soil sampling and submissions. Please note that pre-circulation for your drawing package is not part of the drawing circulation task.

11.1. Roles And Responsibilities

11.1.1.1. Landscape Development Inspector

Refer to the City's Design and Construction Standards, Volume 5, Section 02910, 2.4.

- Reviewing and confirming proposed sample locations within 5 days upon receiving the sampling location plan from the Consultant meets the

2024 Landscape Inspector Guidelines

requirements outlined in the Standards. Confirmation will either be verbal or written to the consultant.

- Reviewing the lab analysis report supplied with the CCC application and verifying that it meets the topsoil standards for specific end-use.

11.1.1.2. Developer / Consultant

Refer to the City's Design and Construction Standards, Volume 5, Section 02910, 2.4.

- Prior to sampling, the Consultant or Contractor shall submit the proposed sampling locations map with the site address to the Landscape Development Inspector via [the 2024 Landscape Development Intake Requests Form](#) for location approval ([Appendix M](#)).
- Follow the procedure outlined in the City's Landscape Design and Construction Standards, Section 02910, 2.4.
- Ensure topsoil meets the parameters outlined in Table 2 of the City's Construction and Design Standards, Topsoil Types and Associated Topsoil Properties Recommended for End Uses.
- Submit test results for the application of CCC.
- Please ensure that the calculations for the soil testing locations are included on the landscape drawing PDF along with the corresponding calculations.

11.1.1.3. Contractor

- Construct the improvement as per approved Engineering Drawings.

11.2. Soil Testing Procedure

The Consultant shall submit a landscape plan with soil testing locations via [the 2024 Landscape Development Intake Requests Form](#) ([Appendix M](#)) prior to site construction for Landscape Development Inspector approval. This request can happen as early as once the drawings are approved. The Landscape Development Inspector must respond within 5 Days or sampling locations will be deemed approved.

2024 **Landscape Inspector Guidelines**

The collection of required samples shall be based on area and end-use. These samples must be submitted to a City-approved commercial laboratory.

The laboratory analysis results must include soil type (texture), pH, Electric Conductivity (EC), Organic Matter (OM) percentage, and nutrient content. All samples are to include a signed Chain of Custody form.

Upon receiving the results, ensure that soil samples meet specific end-use requirements outlined in Table 2 of the Standards. If the sample results do not meet the specifications, amend the soil as necessary to meet the parameters.

Soil test results may be provided to the Landscape Development Inspector prior to CCC application using the 2024 Landscape Development Intake Requests Form request how formal approval for results will not be provided at such time.

Topsoil test results will be required for each specific Municipal Improvement with your CCC application.

To ensure the accuracy and verification of the data, please ensure that the **calculations for the soil testing locations are included on the landscape drawing PDF** along with the corresponding calculations. This will enable a thorough review to confirm the correctness of all details provided.

12. **AUDIT INSPECTIONS & MAJOR MILESTONES**

The objective of conducting site visits during construction is to guarantee that the procedures being employed will result in a functional and successful site, as well as to provide assurance to the Landscape Development Inspector that the site is being built in accordance with City Standards. These inspections can encompass, among others, physical examinations, assessments from vehicle drive-bys, conversations with the Contractor/Consultant, taking measurements and conducting sampling and/or testing, as required. Another purpose of these site visits is to confirm that the appropriate construction techniques are being utilized, thereby minimizing the occurrence of issues prior to the official inspection.

12.1. **Audit Inspection Procedures**

Audit Inspection procedures are a set of processes that are designed to verify that the landscaping construction work is being performed in accordance with the approved Engineering Drawings, landscaping drawings, specifications, as well as applicable laws and

[\(back to top\)](#)

2024 **Landscape Inspector Guidelines**

regulations. These procedures involve a detailed review of construction work and materials. During an Audit Inspection, the Landscape Development Inspector will document observations, identify deficiencies and non-conformities and communicate their findings to the Consultant for corrective action. Audit Inspection procedures are typically an important part of construction quality assurance programs, and are intended to ensure that construction work meets the required standards of quality and safety.

Prerequisites required for an Audit Inspection to occur, with the exception of Natural Areas (refer to [Section 24](#)), are:

- **Approved Engineering Drawings**
- **Signed Servicing Agreement**

12.1.1.1. Audit Inspection Timelines

- Audit Inspections can occur prior to and at any time during landscape construction or during the Warranty Period, based on weather conditions.
- Audit Inspections may be done randomly and informally to monitor construction progress, based on the Landscape Development Inspector's schedule, current location, and available time.
- Audit Inspections are done independently by the Landscape Development Inspector. The Consultant is not required to be present during the audit, but they are free to attend if preferred.
- The Contractor's schedule will not be impeded by Audit Inspections.

Audit Inspections that may be conducted upon request include but are not limited to:

1. **Rough Grade Inspection:** involves assessing the site for proper slope, drainage, and erosion control measures.
2. **Shrub Bed Inspection:** confirm the location, shape, depth, and soil type of shrub beds, and ensure they comply with approved Engineering Drawings. Additionally, the Landscape Development Inspector will ensure that the beds are free of weeds, debris, and excessive compaction.
3. **LID (Low Impact Development) Inspection:** verify proper compaction and gradation of soil. Please refer to [Section 25.0](#) of this document for further details.
4. **Tree Planting:** review the tree planting process and evaluate key FACTors including the placement of the root ball within the excavated tree pit, proper folding of burlap

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

and basket to one-third from the root flare, excavation of soil to the tree stem's root flare, and scarification of the tree pit's sides. The goal is to ensure that the tree is planted in accordance with the standards outlined in the latest City of Edmonton Design and Construction Standards, Volume 5: Landscape and the approved Engineering Drawings.

12.2 Major Milestones

Major Milestone site visits are conducted at certain points of the construction process. Major Milestones include activities that need to be seen prior to construction completion (ie. trenching). Major Milestone site visits will not hold up the Contractor's schedule as long as proper coordination between the Contractor and Consultant occurs and sufficient notice is provided.

The Consultant will be required to provide the Landscape Development Inspector with a minimum of two (2) business days notice of the commencement of the construction of the milestone via the [2024 Landscape Development Intake Requests Form \(Appendix N\)](#) for the following Major Milestone events:

- Trenching / Coring
- Root Barrier
- Natural areas or Existing Landscape Features prior to construction (such as sites adjacent to ER, MR, tree stands, etc.). Refer to [Section 23.0 of this document](#). Natural Area pre-disturbance assessments must be completed a minimum of 4 weeks prior to the commencement of any construction activities.
- Soil Cells
- Playground (see [21.3.1](#) for Hardstops)
- Amenities (see [19.3](#) for Hardstops)

The Landscape Development Inspector's top priority will always be to attend the CCC and FAC Inspections. Therefore, it may not be possible for the Landscape Development Inspector to see all Major Milestone construction events.

In order for the Landscape Development Inspector to be aware of the status of the site, the Consultant must notify them of Major Milestone construction events. If the Landscape Development Inspector believes that the site may not fully comply with the approved

2024 Landscape Inspector Guidelines

construction requirements, the Landscape Development Inspector may request that the asset be removed and replaced. With this in mind, the Major Milestone construction should be documented by the Consultant to represent the type, quality, and method of construction used during the construction event. It is recommended the Consultant provide photos during the construction of any Major Milestone to demonstrate proper construction practices are being applied.



Trenching



Root Barrier

2024 Landscape Inspector Guidelines



Tree Planting



Improper Tree Planting



Proper Root Ball Size



Root Ball is Too Small



Soil Cell Installation

12.2.1 Tree Trench Audit

Refer to detail LA113 Typical Tree Root Trench in the City's Design and Construction Standards, Volume 5: Landscape.

The Landscape Development Inspector requires verification that the boulevard construction matches what is indicated on the approved Engineering Drawings. Inspecting tree trenching/coring is difficult to do when the site is already constructed. Therefore, the Landscape Development Inspector will need to verify the following:

- Depth of trench
- Scarification of the trench
- Width based on the type of roadway
- Proper topsoil type based on its end use is installed

2024 Landscape Inspector Guidelines

It is recommended that photos with scale references be taken during the tree trenching construction and for the Consultant to forward these photos to the Landscape Development Inspector for reference. As a guideline:

- Photographs should be provided every 20m along the length of the boulevard or area that is being trenched as the site is being constructed.
- Photos need to include the measuring tape showing the depth and width measurements of the tree root trench.
- Markers should be positioned along the trench to help distinguish the location where the photo was taken.
- Visual markers should also be used to reference the scale of the trench and the immediate surroundings which aid in the verification of length and depth of the trench.
- All photos must be provided as part of the inspection application in ePlan (if the Landscape Development Inspector did not conduct a site visit during construction), prior to the beginning of any CCC Inspections.



Trenching

12.2.2 Root Barrier Installation

Inspections involve evaluating the root barrier's location, depth, and integrity to ensure that it adequately restricts tree root growth and prevents damage to hardscape elements.

12.2.3 Natural / Existing Landscape Features

Landscape Development Inspectors will:

- Assess the site for compliance with natural area management plans; control of weeds as per Alberta Weed Control Act; absence of stockpiling and dumping; and, ensure the site is in its intended natural state. The site is to be left in a satisFACTory state that meets the City's expectations of safe, and functional for natural areas and shall be maintained as per the Servicing Agreement and Natural Area Management Plan.
- Ensure that the work is complete in accordance with any Federal and Provincial regulations and laws such as Migratory Birds Convention Act, Wildlife Act, and any applicable others.

12.2.4 Soil Cells

Landscape Development Inspectors will review the installation of the soil cells to ensure the location, layout, and depth are as per plan. Review of materials used will also be assessed to verify it matches approved plans.

13. **IN-FIELD DESIGN CHANGE REQUEST**

Any Landscape In-Field Design Changes that occur prior to construction, during construction, or during the maintenance period after the drawings have been approved, must be requested through the ["Landscape In-Field Design Change Request Form"](#).

The link can be found on the City of Edmonton website:

- All change requests will be responded to within 3 business days via email.
- Design changes may include, but are not limited to, in-field design changes to fencing, species change, location of plant material, etc.
- The information submitted in the form will be used by the City of Edmonton to review, reference, and evaluate the design change request. Further discussion may be required between all parties before acceptance and approval of the requested change.

2024 **Landscape Inspector Guidelines**

- Applications for CCC/FAC that have required a Landscape In-Field Design Change, must include the drawings referencing the approved change (pdf) along with the last City of Edmonton stamped approved drawing.

PART 3: INSPECTIONS AND CERTIFICATIONS

14. SERVICING AGREEMENT

Municipal Improvements and their terms of certification are defined in the Project's Servicing Agreement and will be assigned to the area Landscape Development Inspector to inspect and approve the certificate.

14.1. Roles And Responsibilities

14.1.1. Landscape Development Inspector

The Landscape Development Inspector will ensure that the Municipal Improvements completed by the Developer and their representatives meet the requirements and standards set forth in the Servicing Agreement and approved Engineering Drawings. Duties include conducting site inspections, reviewing documentation, and certificate approvals and are further detailed below:

- Act as a point of communication between the Developer and their representatives and the City and will respond to any concerns or issues that may arise.
- Conduct inspections of the landscape Municipal Improvements during the CCC and FAC process to verify that the landscaping has been installed in accordance with the Servicing Agreement, the approved Engineering Drawings and any relevant specifications.
- Work with the Developer and their representatives to address any deficiencies or issues identified during the inspection and ensure that the landscaping meets the City's Standards and approved Engineering Drawings.
- Assess the quality of the hard and soft landscaping installation.
- Review documentation related to the landscaping installations, such as Maintenance Logs and warranty information, to ensure that the Developer has met all of their obligations under the Servicing Agreement.

14.1.2. Developer/Consultant

When obtaining a certificate for a Municipal Improvement, the Developer / Consultant shall ensure compliance with all applicable regulations and standards, conduct required inspections, address any deficiencies or issues that arise and provide a Warranty Period during which they are responsible for addressing any defects or issues. Other responsibilities include:

- Submit all necessary documentation and obtain approvals from relevant authorities for the proposed Municipal Improvement during the pre-construction phase.
- Ensure that the Municipal Improvement is constructed in accordance with approved plans and specifications, as well as any applicable laws and regulations during the construction phase.
- Ensure that all required inspections are conducted and any deficiencies are addressed promptly.
- Apply for a CCC when construction is complete. This involves submitting an inspection application, along with any required documentation, to demonstrate that the Municipal Improvement meets all applicable requirements and is in compliance with all relevant regulations and standards and the approved Engineering Drawings.
- Provide maintenance during the Warranty Period and address any defects or issues that arise with the Municipal Improvement following the issuance of the CCC.
- Ensure compliance with City Policy [IPM Policy C501A](#), [Pesticide Use Notification Form](#) must be filled out for City review and approval.
- Apply for FAC certification just before the Warranty Period expires.
- Conduct quality assurance checks throughout the project lifecycle to ensure that the project is meeting the required standards and specifications.
- Complete all required closeout procedures, including final inspections, obtaining necessary approvals, and providing all required documentation to the City.

14.1.3. Contractor

The Contractor shall:

- Build the project according to the approved Engineering Drawings and specifications, and ensure that all applicable regulations and standards are followed.
- Ensure that the site is safe for workers and the public and that all workers on the construction site follow safety procedures and guidelines.
- Conduct quality control checks throughout the construction process.
- Ensure that any defects or issues that arise are addressed in a timely and effective manner.

It should be noted that a Warranty Period comes into effect after the CCC certificate is issued. During the Warranty Period, the Contractor is responsible for addressing any defects and maintaining the site as per the City's Design and Construction Standards for FAC certification when the Warranty Period ends.

15. CONSTRUCTION COMPLETION CERTIFICATE (CCC)

When the Municipal Improvement, as outlined in the Servicing Agreement, has been completed as per the approved Engineering Drawings, the Developer/Consultant can initiate the certification process. A CCC will be approved when the Municipal Improvement satisfies the Servicing Agreement and is constructed in accordance with the approved Engineering Drawings and the City's Design and Construction Standards.

Refer to [Appendix C](#) for the complete Landscape Inspection Checklist.

15.1. CCC Inspection Season

Inspections for landscape CCC will be conducted by the City's Development Inspections Unit from June 1 to October 15. This window of time may be extended one week at a time, based on a review of the weather forecast, at the Landscape Development Supervisor's discretion. It is important to note that inspections are weather dependent.

2024 **Landscape Inspector Guidelines**

Inspections will be scheduled chronologically once the pre-screen is approved. At the end of the season, inspections will be completed as time permits, pending on schedule availability and weather.

The following criteria will result in the end of the CCC Inspection season:

- Snow accumulation greater than 5cm in the last two weeks of the season, and/or
- Multiple consecutive daytime temperatures below zero degrees Celsius leading up to the CCC season deadline.

15.2. Preliminary CCC Inspection

Please note that preliminary CCC landscaping inspections are no longer being conducted by the Landscape Development Inspector due to time constraints.

The Developer and their representatives are required to have their own preliminary CCC Inspections as indicated in the Project's Servicing Agreement. The templates for the consultant pre-inspection report and (optional) checklist are available in [Appendix G](#).

15.3. Consultant Requirements Prior To CCC Application

Prior to the CCC application, the Developer/Consultant must:


- Ensure the improvement is ready to be inspected (clean, accessible and unobstructed).
- Ensure all work is concluded and construction is complete as per the approved Engineering Drawings.
- Formally acknowledge that the improvement is complete and is free of safety hazards, operational and functional. This will be confirmed in the "Pre-Inspection Report and (optional) Checklist" supplied with the application for inspection. Note, this "Consultant Pre-Inspection Report and (optional) Checklist" is to be conducted within 30 days of applying for CCC inspection and noted on the report. (See [Appendix G](#)).
 - All plant material that is not acceptable is to be identified on the report and is to be rectified prior to inspection.

2024 Landscape Inspector Guidelines

- General comments made on the report with no other specific concerns will not be accepted. In the instance where there are no deficiencies, please indicate no deficiencies on the report

15.4. CCC Inspection Application

The CCC Inspection request must be initiated through eServices. An upload of supporting documents to the Inspection Documents folder of the specified ePlan Municipal Improvement is required.



The upload to ePlan must include:

- CCC Landscape Inspection Request Form
- Consultant Pre-inspection Report and (Optional) Checklist (See [Appendix G](#))
- The latest City approved Engineering Drawings (and/or Redline Drawings). If any changes have occurred from the approved Engineering Drawings, upload the approved updated plans. Failure to not provide the updated plans may result in an incomplete inspection and CCC rejection.
 - Applications for CCC that have required a Landscape In-Field Design Change Request, must include the drawings referencing the approved change (pdf) along with the last City of Edmonton stamped approved drawing
 - The drawings must be highlighted in green to identify the scope of the inspection, matching the specified improvement within the Servicing Agreement. (Refer to [Appendix H](#)).
 - Where amenities are included as part of the Municipal Improvement, highlight each amenity and detail pertinent to that improvement. This is required to ensure that the Landscape Development Inspector coordinates a joint inspection with an Infrastructure Maintenance Inspector for the amenities.

2024 Landscape Inspector Guidelines

- Do not use the color red to highlight as this may get confusing with redlined drawings.
 - Highlight the elements being requested for inspection in green. The highlighting needs to be translucent so that the plan elements are visible and not covered.
 - Only the landscape elements pertaining to the improvement along with the details and corresponding plant list are to be highlighted.
 - The drawings must be submitted in a single PDF document.
 - Include grading drawings, seed mix breakdown, details sheet and any other pertinent information in the submission.
- Soil sample testing results if the Municipal Improvement was initiated into circulation after April 1, 2021.
 - Any other required documentation such as photos of site installations.

Once the upload is complete, the Landscape Development Inspector will accept the task in ePlan and conduct a review of the submission package. If the document submission is in order, the Landscape Development Inspector will approve the ePre-Screen task and schedule the CCC Inspection.

See link for eServices instructions: [eServices User Manual](#)

See link for ePlan best practice: [City of Edmonton ePlan Best Practices for Consultants](#)

2024 Landscape Inspector Guidelines



Construction Not Complete



Site Too Wet



Ready Site (Boulevard)



Ready Site (Outfall)

15.5. CCC Inspection

The City will conduct the CCC Inspection within 30 days of the approved pre-screen.

For the on-site inspection, the following will occur:

- The Consultant and the Landscape Development Inspector will individually mark up their own Inspection Report.
- The Consultant and the Landscape Development Inspector will compare notes during and/or immediately after the inspection to discuss and confirm the deficiencies.
- The Consultant shall take photos of the Landscape Development Inspector's inspection report after the inspection is complete, for reference.
- The Consultant shall provide their markup plan to the Landscape Development Inspector.
- The Landscape Development Inspector will share, via email, their inspection report with the Consultant, if requested, in order to confirm the noted deficiencies during the CCC Inspection process.

If additional deficiencies are discovered after the CCC Inspection:

- The Consultant will have 14 days to complete the repairs for deficiencies, as required, and request a re-inspection.
- A re-inspection will be requested through [the 2024 Landscape Development Intake Requests Form](#) (refer to [Appendix N](#)).
 - No new deficiencies will be added to the list during the re-inspection, unless the deficiencies occurred between the initial inspection and re-inspection, and it creates an issue with safety, design or function..

Only one re-inspection will be permitted during the inspection process. If the identified deficiencies from the inspection are not rectified for the re-inspection, the inspection will be rejected on eServices and the Consultant will have to re-apply and request another inspection.

2024 Landscape Inspector Guidelines

If the Consultant needs additional time to amend the deficiencies prior to the deadline, they may request, using the Google Form, to extend the re-inspection deadline. Extensions may be granted at the Landscape Development Inspector's discretion, keeping in mind that the CCC deadline is October 15th, subject to weather.

When the inspection process is completed, the Landscape Development Inspector will input the inspection result in eServices. In certain circumstances, the inspection can be backdated to the last inspection date.

The Warranty Period will start once the inspection is approved in eServices.

15.6. CCC Inspection Appeal Process

If, for any reason, there is a disagreement with the observations of the Landscape Development Inspector, the Developer/Consultant may request a review of the deficiencies list by the Landscape Development Supervisor. The Developer/Consultant shall collect documentation for the deficiencies in question and present them to the Landscape Development Supervisor within 14 days of the initial CCC Inspection. Upon review, the Landscape Development Supervisor, along with the Landscape Development Inspector that conducted the initial CCC Inspection and Developer/Consultant will re-inspect the entire site within 14 days of the appeal. It should be noted that the Landscape Development Supervisor may note additional deficiencies to be added to the list or may remove deficiencies from the list. This version of the deficiencies list will be deemed final and no other appeals will be granted.

15.7. CCC Documentation Requirements

When the Landscape Development Inspector inputs the site inspection result in eServices, the documentation package must be submitted by the Developer/Consultant within 30 business days of the approved CCC Inspection. If the Consultant does not complete the task within the 30 business days timeline, the inspection approval will expire in eServices, at which time the Consultant will have to reapply for CCC and the process will restart.


If an extension is to be requested, the Consultant will be required to provide written documentation to the Landscape Development Inspector as to why the extension is being requested. The City is required to review the complete documentation package within 60 days of submission. If the CCC documentation package is submitted between June 1 and October 15, then the City shall have ninety (90) days to provide a review.

2024 Landscape Inspector Guidelines

The required submission for the CCC documentation package in ePlan includes:

- Maintenance Schedule
 - Used by the Landscape Development Inspector during the Maintenance Period (between CCC and FAC) to plan their Audit Inspections
- **As-Built Drawings if the Servicing Agreement was signed in 2024**
 - Approved & accepted by the City of Edmonton, in PDF with professional signature and date stamp
 - AutoCAD file to match PDF
 - As-Built Paperwork ([Common Accuracy Items in As-Built Paperwork](#))
- Soil Test Result
- Any other relevant testing results (if required)
- Updated Maintenance Logs (if required)
- Other supplemental information requested by the Landscape Development Inspector for certificate approval.

The following provides a guide on where the documents should be uploaded in ePlan:



If a documentation package is submitted and conforms to all requirements, the department review will be approved by the Landscape Development Inspector by marking the ePlan task accordingly.

A documentation package that does not conform to the above-noted requirements is considered deficient. The CCC will not be approved until all deficiencies have been addressed in the documentation package submission.


If correct documentation is not uploaded in ePlan within 30 business days, or after three attempts are made to submit and the submission package still does not meet requirements, the application will be rejected. The Consultant will need to reapply for a new inspection, within the inspection season, as per City Standards.

15.7.1 CCC Only Documentation Package

Projects that do not require FAC (excluding fencing), and will be taken over by the City after CCC (ex. Municipal Reserve, Environmental Reserve where no improvement is added), will require a complete and accurate document package submission at CCC application.

When FAC is not required for the Municipal Improvement, the required CCC documentation package submission in ePlan includes:

- Asset Cost Form (ACF)
- As-Built Drawings (refer to [Appendix K](#))
 - Approved & accepted by the City of Edmonton, in PDF with professional signature and date stamp
 - AutoCAD file to match PDF
 - As-Built Paperwork ([Common Accuracy Items in As-Built Paperwork](#))
- Maintenance Logs (as required)



15.8. CCC Process Flow Chart

A visual representation of the CCC approval process is shown below. The Project's Servicing Agreement provides additional information if required.

2024 Landscape Inspector Guidelines




Figure 1: CCC Inspection and Documentation Review Process

16. LANDSCAPE INSPECTION DEFICIENCIES

Any fault or defect that impedes functionality poses a safety hazard, does not meet City Design and Construction Standards or deviates from the approved Engineering Drawings is considered a deficiency.

Refer to [Appendix C](#) for the complete Landscape Inspection Checklist for CCC.

16.1. Sod, Shrubs And General

For turf, ensure that:

- Correct sod/seed mix is used;
- No safety hazards exist;
- Sod is even with adjacent surFACes;
- Weeds are controlled; and
- Low points are regraded for proper drainage.

For shrubs/perennials, ensure that:

- Plants are healthy and placed according to plan, with optimal spacing and bed size for mowers to pass through; and
- Bollards or light standards are incorporated within the bed and no mulch is installed below flood lines.

In general, the Contractor must ensure that:

- There are no safety concerns outstanding;
- All Municipal Improvements are installed in accordance with the approved Engineering Drawings and with proper offsets;
- There are no encroachments on City property;
- Erosion and sediment control measures are installed;
- Debris is removed from the site; and.

- Grading has positive drainage.

Remediation must be done for damaged landscaping, and laydown restoration should be done to restore the land to a natural and healthy state.

16.2. Tree Inspection Deficiencies

Edmonton's City Council has the mandate to increase the overall urban tree canopy coverage in Edmonton by 20 percent. Trees provide ecological, social, and economic benefits to the City and its citizens. Trees are a very important and complex element of the urban landscape and deserve special consideration. The following sections provide details on specific areas of concern that should be taken into consideration when inspecting trees.

The Landscape Development Inspector will assess the tree's vitality and structure/form, and will check for pests or diseases. If there is an excessive display of one or a combination of several FACTors, even to a lesser degree, the tree may be rejected. Promptly addressing any deficiencies identified during the inspection is necessary to ensure the safety and health of the tree and its surroundings.

16.2.1. Pests and Disease

Pests and diseases on trees often have common indicators such as physical damage to the tree (i.e. an exit hole, a gallery, pests feeding on the leaf, and/or lesions in the leaf). A symptom is a tree's response to an insect or disease such as dead branches, thinning of the crown, and/or premature yellowing of the foliage. If there is uncertainty about what type of pest or disease is present, a sample can be taken from the tree and provided to a pest diagnostics lab by the Consultant and the results forwarded to the Landscape Development Inspector for reference.

The following actions should be taken when a pest or disease is found in a tree:

- If an active infestation of an insect or a disease is found on a tree at the time of inspection, the tree will be rejected as this is evidence of present activity by that organism, which is visible in, on, or under the canopy, or in or on debris under the tree.
- If signs or symptoms of insect or disease are present on a tree at the time of inspection, the tree may be rejected, at the discretion of the Landscape Development Inspector.

2024 **Landscape Inspector Guidelines**

- If the level of infestation can be controlled then it is up to the Consultant and/or Contractor to determine an appropriate treatment plan and to perform the treatment. The Consultant and/or Contractor must provide a copy of the treatment plan and all logs of all treatments performed to the Landscape Development Inspector via ePlan. The Landscape Development Inspector will re-inspect the tree after treatment is completed. It should be noted that the Landscape Development Inspector may reject the tree after treatment is applied if the level of infestation is not deemed controlling.
- Should a [Regulated Pest](#) be present, then all necessary procedures defined by the Canadian Food and Inspection Agency shall be followed.
- Should a [Named Pest](#) be present, then all necessary procedures defined by the City's Community Standards Bylaw 14600 shall be followed.

16.2.2. Tree Vigor

Tree vigor describes a plant's resilience under environmental stressors. It encompasses the overall health, growth capacity, and stress resistance of the tree.

The following FACTors are used in determining overall tree vigor:

- Evidence of insects and/or disease
- Decay
- Dieback/Deadwood
- Year-to-year comparison of internodal growth
- Appearance, density, and form of buds
- Foliage size, colour, and condition
- Canopy density and coverage
- Presence of epicormic growth and suckers
- Abundance of cones in young conifers
- Seed and fruit production in seedless/fruitless deciduous varieties as well as an abundance of fruit/seed production across deciduous varieties

16.2.3. Tree Structure and Form

Tree structure and form refer to the shape or growth habit of a tree. There are many different tree forms, each with its own distinctive characteristics. Tree structure, along with tree vigor, is utilized to comprehensively assess the health potential of the tree.

Some common tree forms include:

- Columnar: These trees feature a tall, narrow shape, with branches growing vertically
- Conical (Also known as Pyramidal): These trees exhibit a cone-shaped form, with a single dominant trunk with upward-outward branching
- Weeping: These trees have drooping branches that create a flowing, cascading appearance.
- Spreading: These trees have a broad, spreading canopy, with branches that grow outward and downward.
- Vase-shaped: These trees have a broad, open canopy that flares out at the base, resembling a vase.

The form of a tree can be influenced by a variety of FACTors including genetics, pruning activities, and environmental conditions. Tree form can have important practical and aesthetic implications such as determining how much space a tree will require; how it will interact with other plants and structures in a landscape; and, what kind of visual impact it will have.

The following FACTors are used in determining tree structure and form:

- Crack: The separation of wood fibres and predisposed to failure
- Included Bark: This occurs when two stems or branches grow closely together and the bark grows inward, forming a V-shaped crotch. Included bark can weaken the union between the stems or branches and increase the risk of breakage
- Codominant Stems: Two or more stems of approximately the same size arise from the same union

2024 Landscape Inspector Guidelines

- **Narrow Branch Angles:** This occurs when a branch grows at a narrow angle from the trunk or main stem, rather than a wider, U-shaped angle. Narrow branch angles can weaken the branch attachment and increase the risk of breakage
- **Overextended Branches:** This occurs when a branch grows too long without adequate support from other branches, resulting in a weak attachment point that can break easily
- **Trunk Injury:** Injury affecting tree health
- **Poor Trunk Taper:** This occurs when the diameter of the trunk does not decrease gradually as it moves upward, resulting in a weak point in the tree's structure. Exposed tree collar
- **Poor Structure:** When the tree's structure is deformed and defective/unsightly and not properly pruned or maintained, it may develop weak branches or a lopsided crown, which can increase the risk of damage from high winds or heavy snow
- **Crown Imbalance:** This occurs when one side of the tree's crown is significantly larger or heavier than the other, putting extra stress on the weaker side
- **Crook, Sweep in the Trunk;** This is characterized by a leaning lower trunk and a more upright top
- **Tree Root Issues:** The roots of a tree may show signs of damage or decay, which can lead to instability and potentially cause the tree to fall. Signs of root issues may include soil heaving, soil erosion, and exposed roots

16.2.4. Examples of Some Common Tree Deficiencies



Sawfly



Black Knot



Ash Borer



Birch Leaf Miner

2024 Landscape Inspector Guidelines



Epicormic Growth



Small Leaves and Thin Crown



Crown/Root Gall



Pitch Moth

2024 Landscape Inspector Guidelines



Dessicated Aspen



Heavy Seed Crop



Thin Canopy (Recently Installed)



Thin Canopy and Light Coloured Foliage

17. WARRANTY PERIOD MAINTENANCE

The Warranty Period begins upon CCC approval, during which time the Developer must conduct maintenance activities, repair deficient areas, and maintain the Municipal Improvement in accordance with the Project's signed Servicing Agreement and the City's Design Construction Standards. The Developer/Consultant is responsible for repairing any damage or deficiencies within 30 days of written notification from the City, except for items identified as exceptions in the Servicing Agreement. If deficiencies are not repaired and FAC is not obtained within the prescribed timelines, the City may draw on the security holdback to carry out the repairs.

The Developer must establish and maintain all plant material and turf areas in acceptable, vigorous, and healthy growing conditions. The Consultant/Contractor must conduct regular inspections, respond to complaints, make necessary repairs, provide maintenance services, and document all work performed during the Warranty Period, per the City's Design and Construction Standards, Volume 5, Section 4.9.

Safety concerns during the Warranty Period should be immediately repaired.

The maintenance start date will correspond to the on-site CCC Inspection approval date.

Some deficiencies noted during the CCC Inspection are allowed to be repaired during the Warranty Period. These exceptions are permitted at the discretion of the Landscape Development Inspector and must be clearly noted on the Deficiency Plan.

Deficiencies noted during inspections may include, but are not limited to:

- Maintenance pruning
- Structural pruning, as outlined by the Landscape Development Inspector
- Prohibited noxious weeds must be destroyed. Noxious weeds must be controlled by means of inhibiting the growth or spread, or destruction. Refer to the [Alberta Weed Control Act](#) for additional information.
- Minor straightening of tree stakes
- Some turf deficiencies (minor ruts, snow grader damage, etc)
- Trip hazards - must be remediated immediately as a safety concern
- Unacceptable ruts - may be classified as a trip hazard.

The Warranty Period Maintenance Log shall include, but not be limited to, the following information:

- Watering (Date, Time, Volumes, Locations, Duration)
- Turf (Date, Time, Locations, Activity ie: mowing, reseeding)
- Fertilizing (Date, Time, Locations, Product, Volumes)
- Tree/Shrub (Date, Time, Locations, Activity ie: replacements, mulch, tree stakes)
- Weeding (Date, Time, Locations)
- Litter removal (date, Locations)

The Maintenance Log shall be provided individually for each Municipal Improvement vs for a stage.

If subcontractors were used during the maintenance of the project, the Contractor must coordinate with them to ensure that any defects or issues related to their work are addressed during the Warranty Period.

18. FINAL ACCEPTANCE CERTIFICATE (FAC)

At the end of the Warranty Period, the Developer/Consultant may apply for a Final Acceptance Certificate (FAC). Upon approval of the FAC, the City will take the asset into the City of Edmonton inventory and all responsibility for the maintenance of the work will transfer to the City.

Before the FAC is issued, the entire Municipal Improvement must be in conformance with the Project's Servicing Agreement and inspected for the establishment, as per the City's Design and Construction Standards.

18.1. FAC Inspection Season

Inspections for Landscaping Final Acceptance Certificates (FAC) will be conducted by the City's Development Inspections Unit from June 1 to September 30, weather dependent. This window of time may be extended one week at a time, based on a review of the weather forecast, at the Landscape Development Supervisor's discretion. It is important to note that inspections are weather dependent.

2024 **Landscape Inspector Guidelines**

Landscaping projects with a FAC anniversary date that falls after August 1 are eligible for early inspection between August 1 and the end of the FAC season. **The Consultant and Contractor are responsible to maintain the site (should it be approved) for the remainder of the Warranty Period.**

The City may conduct audits before June 1st, weather permitting (with Landscape Development Inspector's discretion).

Inspections will be scheduled on a first-come, first-served basis. At the end of the season, inspections will be completed as schedules and weather permit.

The following criteria will result at the end of the FAC Inspection season:

- The occurrence of "Hard Frost"
 - Hard Frost is defined as 4 consecutive hours of below minus 4 degrees Celsius, as reported by Environment Canada Weather Site.
 - Should Hard Frost occur, the FAC Inspection season will end for calliper trees to be accepted into City's inventory.
- Snow accumulation greater than 5cm in the last two weeks of the season.
- Multiple consecutive daytime temperatures below zero degrees Celsius leading up to the FAC season deadline.

Note that in order for trees to be inspected, they must be in full leaf in order to assess their health and vitality.

Inspections for Landscape Amenities and Fencing will be conducted throughout the year, weather permitting. Snow must be cleared from the improvement in order for the Landscape Development Inspector to complete the inspection.

18.2. Preliminary FAC Inspection

Please note that preliminary FAC landscaping inspections are no longer being conducted by the Landscape Development Inspector due to time constraints.

The Development and their representatives are required to have their own preliminary FAC inspections as indicated in the Servicing Agreement. The templates for the consultant pre-inspection report and (optional) checklist are available in [Appendix G](#) of this document.

2024 Landscape Inspector Guidelines

18.2.1. Examples of Sites NOT Ready to Request FAC Inspections



Turf not ready for FAC



Deficient tree well



Construction fencing prohibits inspection of trees and turf




Weeds eradicated for FAC

2024 Landscape Inspector Guidelines



Tree has low vitality and will not be accepted into the City inventory. This tree should have been replaced prior to requesting an inspection



Site not ready as plant material has not been installed prior to the recheck



Site is not ready for inspection

18.3. Consultant Requirements Prior To FAC Application

Prior to the FAC application, the Developer/Consultant must:


- Ensure the improvement is ready to be inspected (clean, accessible and unobstructed)
- Ensure all work is concluded and construction is complete as per the approved Engineering Drawings.
- Formally acknowledge that the improvement is complete and is free of safety hazards, operational, and functional. This will be confirmed in the “**Consultant Pre-Inspection Report and (optional) Checklist**” supplied with the application for inspection. (See [Appendix G](#)). Note, this “Pre-Inspection Report and (optional) Checklist” is to be conducted within 30 days of applying for FAC inspection.
 - All plant material that is not acceptable is to be identified on the report and is to be rectified prior to inspection.
 - General comments made on the report with no other specific concerns will not be accepted. In the instance where there are no deficiencies, please indicate no deficiencies on the report

Once these requirements have been achieved, the improvement will be eligible for FAC Inspection.

18.4. FAC Inspection Application

The FAC Inspection request must be initiated through eServices. An upload of supporting documents to the Inspection Documents folder on the specified ePlan Municipal Improvement is required.

Consultants upload documents to ePlan for FAC pre-screen review in this configuration:



The upload to ePlan must include:

2024 Landscape Inspector Guidelines

- FAC Landscape Inspection Request Form ([Appendix D](#))
- Consultant Pre-inspection Report (See [Appendix G](#))
- The latest City approved Engineering Drawings (and/or Redline Drawings). **If any changes have occurred from the approved Engineering Drawings, upload the approved updated plans. Failure to provide the updated plan may result in an incomplete inspection and FAC rejection.**
 -
 - The drawings must be highlighted in green to identify the scope of the inspection, matching the specified improvement within the Servicing Agreement (See [Appendix N](#)).
 - Where amenities are included as part of the Municipal Improvement, highlight each amenity and detail pertinent to that improvement. This is required to ensure that the Landscape Development Inspector coordinates a joint inspection with an Infrastructure Maintenance Inspector for the amenities.
 - Do not use the color red to highlight as this may get confusing with redlined drawings.
 - Highlight the elements being requested for inspection in green. The highlighting needs to be translucent so that the plan elements are visible and not covered.
 - Only the landscape elements pertaining to the improvement along with the details and corresponding plant list are to be highlighted.
 - The drawings must be submitted in a single PDF document.
 - Include grading drawings, seed mix breakdown, details sheet and any other pertinent information in the submission.
- A Maintenance Log for landscaping improvements.

Once the upload is complete, the Landscape Development Inspector will accept the task in ePlan and conduct a review of the submission package. If the document submission is in

2024 Landscape Inspector Guidelines

order, the Landscape Development Inspector will approve the Pre-Screen task and schedule the FAC Inspection.

See link for eServices instructions:

[City of Edmonton eServices User Manual](#)

See link for ePlan best practices:

[City of Edmonton ePlan Best Practices for Consultants](#)

18.5. FAC Inspection

The City will conduct the FAC Inspection within 30 days of the approved pre-screen.

For the on-site inspection, the following will occur:

- The Consultant and the Landscape Development Inspector will individually mark up their own Inspection Report.
- The Consultant and the Landscape Development Inspector will compare notes during and/or immediately after the inspection to discuss and confirm the deficiencies.
- The Consultant shall take a photo of the Landscape Development Inspector's inspection report after the inspection is complete, for reference.
- The Landscape Development Inspector's notes are based on observed existing conditions at the time of an inspection and are representative of deficiencies observed during that particular active inspection for a particular Municipal Improvement.
- The Consultant may, at their discretion, need to revisit the site to note existing site conditions for the accuracy of the final as-built drawings. The Consultant shall provide a marked-up plan that captures their observations to the Landscape Development Inspector if requested.
- The Landscape Development Inspector may share, via email, the City copy marked-up plan with Consultants, if requested, in order to confirm deficiencies.

If additional deficiencies are discovered after the FAC Inspection:

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

- The Consultant will have 14 days to complete the repairs for the deficiencies, as required, and request a re-inspection
- Request a re-inspection via Google form, [2024 Landscape Development Intake Requests Form \(Appendix N\)](#)
 - No new deficiencies will be added to the list on the re-inspection unless the deficiencies create a safety issue, are significant in nature, or are not completed within 14-days of the previous FAC Inspection date

Only one re-inspection will be permitted during the inspection process. If the identified deficiencies from the inspection are not rectified at the re-inspection, the inspection will be rejected on eServices and the Consultant will have to re-apply and request another inspection.

If the Consultant needs additional time to amend the deficiencies (identified from the inspection only) prior to the deadline, they may request, using the Google Form, to extend the re-inspection deadline. Extensions may be granted at the Landscape Development Inspector's discretion, keeping in mind that the FAC deadline is September 30th, subject to weather.

If the re-inspection is booked by the Consultant and the deficiencies are not repaired for the re-inspection, the site will be rejected and the Consultant must reapply for the re-inspection when the site is ready.

When no deficiencies are noted during the FAC Inspection, the Inspection Result checkbox in eServices will be marked 'approved'.

18.6. FAC Inspection Appeal Process

If, for any reason, there is a disagreement with the observations of the Landscape Development Inspector, the Developer/Consultant may request a review of the deficiencies list by the Landscape Development Supervisor. The Developer/Consultant shall collect documentation for the deficiencies in question and present them to the Landscape Development Inspector within 14 days of receipt of the deficiencies list. Upon review, the Landscape Development Supervisor, along with the Landscape Development Inspector that conducted the initial FAC Inspection and Developer/Consultant will inspect the entire site within 14 days of the appeal. It should be noted that the Landscape Development Supervisor may note additional deficiencies to be added to the list or may remove

2024 **Landscape Inspector Guidelines**

deficiencies from the list. This version of the deficiencies list will be deemed final and no other appeals will be granted.

18.7. Extending Establishment Periods

Establishment of landscapes can be observed and assessed through the general growth level of a specific plant and vegetation over time. Acceptable establishment means an increase in plant and vegetation growth and quality from the time it was planted, whereas a non-established asset remains static or has a decrease in overall plant and vegetation growth. The establishment includes, but is not limited to, being well-rooted and healthy; exhibiting vitality (thriving in the given environment); and, requiring reduced levels of maintenance.

For landscape inspections where FAC is rejected due to deficient plant material, an extended establishment period is required for the site before re-applying for FAC.

The landscape inspection establishment period will be extended until the following growing season for sites with:

- 25 shrubs or less, where 50% or more of the total shrubs have not been established.
- More than 25 shrubs, where 25% or more of the total shrubs have not been established.
- 10% or more of the turf that has not been established:
 - Concentrate bare area is considered as a deficiency and must be remediated.
 - 0.5 m on the arterial road only, deficient plant material will be permitted as an exception to the 10% ratio.
- If over 10% of the trees are rejected and replaced on sites with 41 or more trees, or when tree root balls were disturbed during the current year, the site will be rejected.
- If over 25% of trees are rejected and replaced on sites with 40 trees or less, or when tree root balls were disturbed during the current year, the site will be rejected.

When the site encounters any of the scenarios above, the Developer may re-apply after 12 months of establishment, or August 1st of the following year, as per the City's Design and

[\(back to top\)](#)

2024 **Landscape Inspector Guidelines**

Construction Standards, Volume 5, Section 4.8.2 (Warranty Period). Should the site be rejected because of tree conditions, the Developer may, alternatively, pursue a FAC tree Buyout. Refer to [Section 19.0](#) of this document for more details on FAC Tree Buyout eligibility.

Should a landscape inspection be canceled due to weather or because the FAC Inspection season has ended, the inspection will be scheduled for the following growing season, as soon as the FAC Inspection season begins.

18.8. FAC Documentation Requirements

When the Landscape Development Inspector inputs the site inspection result in eServices, the documentation package must be submitted by the Developer/Consultant within 30 business days of the approved FAC Inspection. If the Consultant does not complete the task within the 30 business days timeline, the inspection approval will expire in eServices, at which time the Consultant will have to reapply for FAC and the process will restart.

If an extension is to be requested, the Consultant will be required to provide written documentation to the Landscape Development Inspector as to why the extension is being requested. The City is required to review the complete documentation package within 60 days of submission. If the FAC documentation package is submitted between June 1 and October 15, then the City shall have ninety (90) days to provide a review.


The required submission for the FAC documentation package in ePlan includes:

- Asset Cost Form (ACF form, .xls format) Can be found at the link below [Landscape Inspector Guidelines | City of Edmonton](#)
- As-Built plans in AutoCAD as one bound file (.dwg)
- As-Built plans in a single PDF (.pdf) The pdf should be searchable, not a scan (See [Appendix K](#))
- Separate Landscape Plan (PDF) indicating the year planted (single searchable PDF) for all trees. Must be indicated on a copy of the as-built drawing (See [Appendix L](#))
- Any other records requested at the time of FAC (ex. Spray logs, correspondence)
 - For playgrounds, a Letter of Warranty for the playground structure and any pour-in-place surFACe is required.

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

The following provides a guide on where the documents should be uploaded in ePlan:



If a documentation package is submitted and conforms to all requirements, the department review will be approved by the Landscape Development Inspector by marking the ePlan task accordingly. This will mark the end of the Maintenance Period and the FAC certificate will be issued and dated for when the FAC Inspection was conducted.

If Revisions Are Required as a Second Submission: upload the updated document using the same file name so it can be viewed as a **new version (ie. V.2)** in order to avoid any confusion.

A documentation package that does not conform to the above-noted requirements is considered deficient. When revisions are required in the documentation package. **The FAC certificate will not be issued until all deficiencies have been addressed in the documentation package submission.**

If correct documentation is not uploaded in ePlan within 30 business days, or after three attempts are made to submit and the submission package still does not meet requirements,, the application will be rejected. The Consultant will need to apply for a new inspection, within the inspection season, as per City Standards.

18.9. Common Accuracy Items In As-Built Drawings

- Correct species and locations
- Correct quantities, including labels and plant lists
- CAD drawings are bound (one .dwg file including refs, base plans, details etc.)
- All sheets are included for area inspected including details specific to the highlighted improvement (See [Appendix K](#))

2024 Landscape Inspector Guidelines

- Only the area being taken into inventory is shown on the as-built. Areas with other improvements can be grayed out, removed from the drawing set, or the improvement in question can be highlighted. It must be clear from the as-built plan which assets are being taken into inventory with the specific improvement.
- If grading has changed from the approved drawing, an updated grading plan must be submitted with the as-built.
- Linework and hatches are shown correctly as required
- ACF form is completely filled out and has correct values and quantities
- Documents submitted are only for the improvement being applied for
- All submitted documentation correspond to each other and accurately reflects the site

18.10. FAC Process Flowchart

- The FAC process flowchart below visually summarizes the steps involved in obtaining an approved FAC from the City. The Project's Servicing Agreement provides additional information if required.

2024 Landscape Inspector Guidelines




Figure 2: FAC Inspection and Documentation Review Process

***DISCLAIMER: This new process is for new municipal improvements with Servicing Agreements signed in 2024**

18.11 LANDSCAPE CCC AS-BUILT DRAWING SUBMISSION PROCESS UPDATE

18.11.1 Introduction:

We are introducing an updated two-phase process for obtaining a Construction Completion Certificate (CCC), effective for all new Servicing Agreements starting January 2024. This document outlines the requirements for each phase, including the introduction of an As-Built documentation phase to ensure accuracy and compliance and FAC update.

18.11.2 Key Changes At A Glance

- **Phase 1:** Initial CCC submission process remains unchanged, focusing on preliminary inspections and documentation.
- **Phase 2:** Introduction of an As-Built documentation phase at CCC level versus FAC with specific spatial tolerance and digital file requirements.
- **Final Acceptance Certificate (FAC):** Updates on documentation submission for the FAC process. No CAD Files required.

18.11.3 PHASE 1: Initial CCC Submission / Inspection / Result

Existing Process (Unchanged): The initial phase remains as it currently is, including all the existing documentation requirements.

The upload to ePlan must include:

- FAC Landscape Inspection Request Form ([Appendix D](#))
- Consultant Pre-inspection Report and (optional) checklist (See [Appendix G](#))

Documentation Requirements(unchanged):

- CCC Landscape Inspection Request Form.
- Pre-inspection Report from Owner/Consultant detailing the readiness and compliance of the project as per City standards.
- Latest City-approved Engineering Drawings (and/or Redline Drawings), with specific highlighting instructions.
- Soil sample testing results (for Municipal Improvements initiated after April 1, 2021).

[\(back to top\)](#)

2024 **Landscape Inspector Guidelines**

- Any other required documentation such as photos of site installations.

Inspection Process (Unchanged):

- The City conducts the CCC Inspection within 30 days of the approved pre-screen.
- Both the Consultant and the Landscape Development Inspector mark up their own Inspection Report.
- A re-inspection process is detailed, including the handling of deficiencies and re-inspection requests within the landscape guideline.

18.11.4 PHASE 2: CCC As-Built Documentation

18.11.4.1 Introduction of New Requirements

A separate CCC phase focusing on As-Built documentation is introduced to enhance documentation accuracy.

18.11.4.2 Spatial Tolerance Requirements for Asset Placement:

- **Tolerance Requirements Near Property Lines or Buried Utilities:**
 - Within 1 meter of a property line or buried utility: Tolerance of ± 0.3 meters.
- **General Tolerance Requirements:**
 - Within 3 meters of a road, sidewalk, multi-use trail, property line, or buried utility: Accuracy of ± 0.3 meters for placement and as-built drawings.
 - Between 3 meters and 10 meters from above reference points: Accuracy of ± 1 meter.
 - Beyond 10 meters from reference points: Accuracy of ± 3 meters.

18.11.4.3 Documentation Requirements:

As-Built Drawing Submission: Submit the As-Built Drawing(s) before January 15 for review. These drawings must also comply with the digital file specifications outlined below.

2024 Landscape Inspector Guidelines

AutoCAD DWG File, where:

- The drawing file is bound (one .dwg file including refs, base plans, details etc.);
- The drawing file must be spatially correct and georeferenced to 3TM-114 grid coordinates (WKID 3776);
- The drawing file must highlight the appropriate area of the municipal improvement and all sheets in the drawing are included for the area inspected including details specific to the highlighted improvement;
- The drawing file has different features and geometry types on different layers, specifically:
 - distinct topographic feature types should be on separate layers (e.g. trees are a different layer than shrub beds, asphalt, etc.),
 - point, polyline (linear), and polygon (area) features should be on separate layers, and
 - annotations, leader lines, title blocks, revision tables, notes, scale bars, borders, or other accessory drawing items must be on separate layers from the feature geometry itself; and
 - 2-dimensional features must be closed polygons (e.g. a paved multi-use trail should be made up of one or more closed polygons, not two lines representing the edges of asphalt).

Searchable PDF File, where:

- The drawing is approved & accepted by the City of Edmonton;
- The drawing is to comply with the City's Design and Construction Standards by an Alberta Landscape Architect; and
- The PDF drawing matches the AutoCAD-format DWG file specified above.
- As-Built plans in a single PDF (.pdf), which should be searchable, not a scan.

Related As-Built Paperwork with:

- Correct species and locations;

2024 Landscape Inspector Guidelines

- Correct quantities, including labels and plant lists;
- Taking care to PDF only the area being taken into inventory is shown on the as-built. Areas with other improvements can be grayed out, removed from the drawing set, or the improvement in question can be highlighted. It must be clear from the as-built plan which assets are being taken into inventory with the specific improvement.
 - Linework and hatches are shown unambiguously and correctly as required on the drawings.
 - If grading has changed from the approved drawing, an updated grading plan must be submitted with the as-built.
- Documents submitted are only for the improvement being applied for.
- All submitted documentation corresponds to each other and accurately reflects the site.

The 'Issue for Construction' (IFC) drawing package, while consolidated, does not accurately represent the project's final state after construction. Therefore, it should not be used as an 'As-built' drawing.

18.11.5 FAC Submissions & Inspection & Result (Unchanged):

The initial phase remains as it currently is, including all the existing documentation requirements.

- FAC Landscape Inspection Request Form
- Pre-inspection Report
- Latest City-approved Engineering Drawings (and/or Redline Drawings) or As-built.
- If any changes have occurred from the approved Engineering Drawings As-built, upload the approved updated plans.
- The drawings must be highlighted in green to identify the scope of the inspection, matching the specified improvement within the Servicing Agreement.
- Where amenities are part of the Municipal Improvement, highlight each amenity and detail pertinent to that improvement.

2024 Landscape Inspector Guidelines

- The highlighting needs to be translucent so that plan elements are visible and not covered.
- Only landscape elements pertaining to the improvement, along with details and corresponding plant list, are to be highlighted.
- The drawings must be submitted in a single PDF document.
- Include grading drawings, seed mix breakdown, details sheet, and any other pertinent information in the submission.

18.11.5.1 Department Review Phase Existing Process (Unchanged):

- **Tangible Capital Asset form (TCA form, .xls format)** Now renamed as **Asset Cost Form to align with Transportation and EPCOR**, retaining the same format.
- **Year Planted Plan:** A separate landscape plan (PDF) Indicating the Year Planted for All Trees
- Any Other Records Requested at the Time of FAC
- This may include additional documentation such as Spray logs, correspondence, etc., that were not part of the initial submission but are relevant to the completed project.

18.11.5.2 *New Requirement*:

- **NO CAD DWG submission is required anymore at this time**
- **Please Update the As-Built Plans in a searchable PDF only**
 - Reflecting any changes or updates made post-CCC by updated As-Built Plans in a Single Searchable PDF (.pdf)
 - Ensure that the As-Built plans are comprehensive and accurately represent the completed project changes only.

PART 4: SUPPLEMENTARY MUNICIPAL IMPROVEMENT INFORMATION

19. FAC TREE BUYOUT PROGRAM

The FAC Tree Buyout Program is an option when trees do not meet the City's FAC acceptance criteria listed in the City's Design and Construction Standards, Volume 5, Section 4.9.2.

In a Buyout, the Developer will pay the City an agreed-upon dollar amount to cover the replacement and/or maintenance cost of the remaining tree deficiencies that are preventing the approval of the FAC.

19.1. FAC Tree Buyout Eligibility

FAC Tree Buyouts will be considered by the City of Edmonton on sites where all of the following criteria apply:

- All deficiencies not identified as part of the Buyout must be remediated prior to proceeding with the site re-inspection.
- The site is over the maximum allowable percentage of rejected and/or deficient trees:
 - For sites with 41 or more trees, 10% of the trees are rejected or root balls disturbed within the current year.
 - For sites with 40 trees or less, 25% of the trees are rejected or root balls disturbed within the current year.
 - Sites requiring pruning maintenance.
 - Additional pest control on trees is required.
- Must have a previously rejected FAC Inspection and the current FAC Inspection would be rejected, if not proceeding with the Buyout.
- All of the required paperwork and payment in the form of a cheque must be submitted within the outlined timelines. Otherwise, the City reserves the right to reject or cancel the Tree Buyout application.

2024 Landscape Inspector Guidelines

NOTE: All trees identified as part of the Buyout Deficiency Plan will be included in the Buyout estimate and must not be replaced or altered for the Tree Buyout to proceed. If the Buyout trees are altered in any way, the site will not be eligible for FAC until the following year.

19.2. Roles And Responsibilities

19.2.1. Landscape Development Inspector

- Confirm with the Consultant that the Municipal Improvement is eligible for a Tree Buyout.
- Provide the cost estimate to the Developer or their representative.
- Review documents for accuracy and completeness.
- Record the Buyout information in the 2024 Landscape Inspector Tracker.
- Approve the FAC Inspection on eServices once payment is received from the Developer.
- File all appropriate documents in the project folder.

19.2.2. Consultant

- Submit the required Tree Buyout documents to the City of Edmonton.
- Ensure all submitted documents are accurate and complete.
- Maintain ongoing communication with the Developer and the Landscape Development Inspector during the Buyout process.
- Ensure all necessary documents and required payments are submitted within the specified timeline.

19.2.3. Developer

- Initiate the Tree Buyout process with their Consultant.
- Authorize the form for the Tree Buyout.

2024 Landscape Inspector Guidelines

- Provide payment to the City of Edmonton within the specified timeline.

19.2.4. Contractor

- Must not replace any trees for Municipal Improvement following the initial FAC Inspection.

19.2.5. Landscape Development Inspector Supervisor

- Sign the appropriate documents.
- Confirm the disbursement of funds with the Development Engineer.

19.3. FAC Tree Buyout Application

All Information and documentation can be found [on the City's Tree Buyout Website](#).

After the initial FAC Inspection, the Consultant must request a Buyout via the [2024 Tree Buyout Application Form](#) for Phase 1 and then Phase 2.

19.3.1. Phase 1 of Tree Buyout Application

Using the [2024 Tree Buyout Application Form](#), the applicant will provide a high-level FAC Tree Buyout application request. The Landscape Development Inspector will confirm whether or not the site is eligible for the Tree Buyout Program within 2 business days.

19.3.2. Phase 2 of Tree Buyout Application

Using the 2024 Tree Buyout Application Form, The applicant must provide the following documents:

- Tree Buyout Deficiency Inspection Plan
 - The plan must highlight and identify only the trees and the specific deficiencies included in the Buyout ([Appendix J](#)).
- Tree Buyout Cost Estimate (from City Forestry)
 - Note, additional Buyout deficiencies identified during the re-inspection may require an updated cost estimate.
- Alberta First Call

2024 Landscape Inspector Guidelines

- Uploading the most recent Alberta First Call data could potentially lower hydrovac costs. This action is optional and can be carried out at the developer's or consultant's discretion in this phase. Should you choose not to upload the Alberta First Call, please note that the cost estimate will be finalized following Forestry's assessment. We recommend downloading the Alberta First Call along with the other buyout application documents in this phase.
- Dig Shaw
 - Please note that Shaw utilities require a separate locate submitted via Dig Shaw; this is because they are not part of the consortium. However, for sites eligible for buyout, please ensure that locates from Dig Shaw are uploaded in addition to the Alberta One Call and other buyout application documents as mentioned above.
- Tree Buyout relocation
 - In the case of a or multiple trees could not be planted part of the buyout process, please provide us with a potential new location within the current stage of the project using [2024 Tree Buyout Application Form](#)
 - Location will be reviewed internally with City Operation Forestry. If further discussions are needed, efforts will be made to reach out for clarification.
- Timeline after documents are uploaded:
 - Within 5 business days City Forestry will provide a Tree Buyout Cost Estimate to the Consultant and a copy to the Landscape Development Inspector for review;
 - Within 10 business days of the initial inspection the Consultant will apply for a re-inspection using the 2024 Landscape Development Intake Requests form. This re-inspection will confirm all non-tree deficiencies are completed and verify that all the tree buyout items are noted on the Buyout Documents;
 - Following the re-inspection, proceed to Phase 3 of the Buyout process to find the timelines for submitting the cheque and the Tree Buyout Declaration Form.

19.3.3. Phase 3 of Tree Buyout Application

Finalization of the Tree Buyout Process will require:

- A complete and signed FAC Tree Buyout Declaration Form from the Developer:
 - A digital copy must be uploaded in the Phase 3 portion of the 2024 Buyout Google Form and a signed physical form **must** accompany the payment.
- The Developer is to submit the cheque, payable to the City of Edmonton, via mail or courier to:
 - Development Servicing Agreement Unit
Attention: (Provide DSA Engineer's Name)
2nd Floor Edmonton Tower
10111-104 Avenue NW
Edmonton AB T5J 0J4.
 - The cheque must be marked, "Tree Buyout + Servicing Agreement Reference Number".
 - **Payment is due within 30 business days after receiving the confirmation of the final cost for the Tree Buyout from the Landscape Development Inspector.**

The Development Engineer will notify the Landscape Development Supervisor when the cheque and signed Tree Buyout Declaration Form have been received. After confirming that the payment amount is correct for the Tree Buyout, the Landscape Development Supervisor will sign the form and notify the Landscape Development Inspector that the signed form is complete and the Tree Buyout is approved. Additionally, the Landscape Development Supervisor will confirm the disbursement of funds with the Development Servicing Agreement Engineer.

The Landscape Development Inspector will update the status of the Tree Buyout / FAC requirement eServices accordingly. The FAC application will then proceed to the Department Review Task on ePlan. Please refer to [Section 18.8](#) of this document for info on the required documentation for FAC and submission procedures.

All documents pertaining to the FAC Tree Buyout Process will be saved in the project folder.

19.3.4 Maintenance End Date

1. The Developer and their representatives will be required to continue maintaining the asset until the Tree Buyout payment, Tree Buyout documentation and approved FAC As-Built documents have been received by the City. The City will be monitoring the site throughout the Maintenance Period and reserves the right to cancel or reject the Tree Buyout Process, should the Developer and their representatives fail to maintain the site, to the safety, function or design of the improvement.

20. AMENITIES INSPECTIONS

Refer to the City's Design and Construction Standards, Volume 5, Section 8.2 (Supplementary Standards, ManuFACTurer's Manual, Servicing Agreement, and Engineering Drawings) as primary inspection guides.

20.1 Roles And Responsibilities

20.1.1. Infrastructure Maintenance (IM) Inspector

- Conduct Hardstop Inspections.
- Conduct CCC and FAC Inspections.
- Provide the Consultant with a written report following the CCC/FAC Inspection.
- Update eServices whether the inspection is Approved or Not Approved.

20.1.2. Landscape Development Inspector

- Review and approve pre-screen and department review submissions in ePlan.
- Assign IM Inspector to the Municipal Improvement in eServices.
- File CCC and FAC Inspection documents, including inspection reports in the project Google Drive.

20.1.3. Transportation Development Inspector

- Review and inspect hard surFACing related to the stage of development.

20.1.4. Developer/Consultant

- Invite applicable stakeholders to a pre-construction meeting, where the scope of work, schedule, timelines and communication plans are discussed.
- Contact the appropriate Municipal Improvement Inspector to arrange Hardstop Inspections prior to CCC Inspections.
- Apply for CCC and FAC Inspections through eServices.
- Upload all required documents for inspection and certification through ePlan.

20.1.5 Contractor

- Construct the Municipal Improvement, as per the approved Engineering Drawings and specifications.

20.2. Pre-Construction Meeting

The Consultant/Developer is required to invite all applicable stakeholders to a kick-off or pre-construction meeting where the scope of work, schedule, timelines, communication plans and any other relevant business will be discussed.

20.3. Hardstop Inspection Application

To schedule a Hardstop Inspection, the Consultant must contact the appropriate Municipal Improvement Inspector via email or phone:

- Brett Chartrand, Infrastructure Maintenance Team Leader Site Furnishing
(Brett.chartrand@edmonton.ca)

The IM and Transportation Development Inspectors will document the required audits using a Construction Hardstop Inspection Form, in which the Consultant must upload a completed form when applying for CCC.

20.3.1. Hardstop Inspection Stages

Required Hardstop	Inspection Team *
Base excavation and sub-base compaction of the sub-base of any hard surFACe.	Transportation Group
Forms and reinforcement	Transportation Group

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

Rebar in concrete slabs if required	Transportation Group
Concrete testing, pouring and finishing	Transportation Group
Amenities inspection - Post contractor installation	Infrastructure Maintenance

***NOTE:** Hardstop Inspections must be requested and the Development Inspector will approve the pre-screen task on ePlan. The CCC Inspection for the amenities will be coordinated by the IM Inspector, directly with the Consultant.

20.4. Landscape Amenities CCC Inspection

The CCC Inspection for landscape amenities will be conducted by the IM Inspector for Municipal Improvement.

The IM Inspector will conduct an on-site inspection to verify that:

- All amenities are installed, as per the approved plan and specification.
- The correct quantity of the amenity is provided and installed at the proper locations.
- All boards, slats, arms, or any other components are securely fastened - no loose or detached elements present.
- Stain colors are accurate and not chipped or faded.
- Waste receptacle lids are attached to the base.
- The amenity is undamaged and fully functional.
- There are no missing parts/components.
- The amenity is mounted on concrete and attached as per the specified details.
- Vandal-proof hardware (tamper resistant and locking) are provided for all site furniture, with a minimum of:
 - One per waste receptacle;
 - Two per bench; and,

2024 **Landscape Inspector Guidelines**

- Two per picnic table.

The Transportation Inspector will conduct an on-site inspection to verify that:

- Concrete is not cracked and/or exhibiting honeycombing;
- The amenity meets required standards for texture, levelness and smoothness; and,
- Dimensions and elevations are as per specifications.

If deficiencies are noted during the CCC Inspection:

- The Consultant will have 14 days to repair deficiencies and request a re-inspection by contacting the appropriate inspectors.
- No new deficiencies will be added to the deficiencies list during the re-inspection unless the deficiencies:
 - Occurred between the initial inspection and the re-inspection;
 - Creates a safety issue; and/or
 - Are significant in nature.
- Only one re-inspection will be permitted during the inspection process. If the identified deficiencies during the inspection are not rectified at the re-inspection, the inspection will be rejected on eServices and the Consultant will have to re-apply and request another inspection.
- If the Consultant requires more time to address deficiencies identified in the inspection before the 14-day deadline, they may request an extension but approval will be at the discretion of the Landscape Development Inspector.
- When no deficiencies are found during the CCC Inspection, the IM Inspector will mark the Inspection Results as 'Approved' in eServices, which will establish the benchmark date for the start of the Warranty Period.
- The Landscape Development Inspector will review and approve the documents uploaded in ePlan and maintain copies of the documents in the project file folder.

20.5. Landscape Amenities Warranty Period

Please refer to the project Servicing Agreement for the specific length of the Warranty Period. The IM Inspector will perform audits following CCC in order to monitor any safety issues or defects in the hardware or structure.

The Developer and their representatives are responsible for maintaining and cleaning waste receptacles until FAC for them is obtained.

20.6. Landscape Amenities FAC Inspection

Refer to [Section 18.8](#) of this document for general FAC Inspection processes and document submission requirements.

The IM Inspector will conduct an inspection to verify that:

- All the amenities are still in place, as per plans and that they are properly attached to a concrete pad.
- All boards, slats, arms, or any other component is securely fastened - no loose or detached elements are present.
- Stain colors are accurate and not chipped or faded.
- Waste receptacle lids are attached to the base.
- Waste receptacles are not overflowing.
- The amenity is undamaged and is fully functional as intended.
- Vandal-proof hardware (tamper resistant and locking) is provided for all site furniture, with a minimum of
 - One per receptacle;
 - Two per bench; and,
 - Two per picnic table.

When no deficiencies are noted during the FAC Inspection, the IM Inspector will mark the Inspection Results as 'Approved' in eServices.

Refer to [Section 18.8](#) of this document for general FAC Inspection processes and document submission requirements. The Landscape Development Inspectors will review and approve the FAC documents uploaded in ePlan and maintain copies of the documents in the project folder.

21. FENCING INSPECTIONS

Refer to the City's Design and Construction Standards, Volume 5, Section 8.3 for general fencing requirements, manuFACTurer's manual, Servicing Agreement, and Engineering Drawings as primary inspection guides.

Fencing installed on City property will require a CCC and FAC Inspection by the Landscape DevelopmentInspector.

Fencing that is installed on private property will only require a CCC Only Inspection, which may be conducted independently by the Developer/Consultant and providing the Landscape Development Inspector with photographs of the fence (**up to 40m**)and its immediate surrounding properties for reference and record-keeping. This applies to wood screens, chain-linked fencing, wildlife fencing, Post and Rail fencing, decorative steel fencing, vinyl fencing, and any other approved styles.

It should be noted that fencing with metal pickets extending beyond the top rail are prohibited and shall not be installed by the Developer.

21.1. Roles And Responsibilities

21.1.1. Landscape Development Inspector

- Conduct a CCC and FAC Inspection for fencing installations on City Property.
- Conduct CCC Only inspections for fencing installations on Private Property.
- Input the inspection results in eServices and file documents in the project folder.

21.1.2. Transportation Development Inspector

- Conduct CCC and/or FAC Inspections for noise attenuation fencing, masonry pillars, and masonry entry features.

21.1.3. Developer/Consultant

- Apply for CCC certification for fencing in ePlan for fences on City Property and via photo submission for fences constructed on private properties.
- Oversee and manage the installation of the fence and ensure that inspection requirements for CCC and/or FAC are satisfied.

21.1.4. Contractor

- Install fencing as per the approved Engineering Drawings.
- Address any deficiencies identified by the Landscape Development Inspector, within the specified timeframe.
- Provide maintenance and repair services during the Warranty Period, as required.

21.2. Fencing CCC Inspection Application

Refer to [Section 15.0](#) of this document for general CCC Inspection processes and document submission requirements. For CCC Only inspections on private property, one re-inspection will be permitted during the inspection process. If the identified deficiencies from the inspection are not rectified at the re-inspection, the inspection will be rejected on eServices and the Consultant will have to re-apply and request another inspection.

For Vinyl, Wrought Iron and Decorative fencing, please submit the most recent approved engineering drawing with complete details. Additionally, provide a link to the manuFACTurer's installation manual or a PDF copy of the detail. Failure to provide these documents may result in the rejection of your application.

The Consultant shall upload the [consultant pre-inspection fencing CCC inspection checklist](#) document to ePlan.

For photo submissions, the CCC application requires additional information, as outlined below.

21.3. Application For Photo CCC Inspection

The Consultant shall upload the following documents to ePlan:

- [Fencing CCC Inspection Checklist for Photo Submission.](#)
- [CCC Inspection Request Form](#)
 - Ensure any deficiencies are noted on the Fencing CCC Inspection checklist for Photo Submission form.
- The latest City approved Engineering Drawings and any other supplementary drawing details:
 - The approved Engineering Drawings must be highlighted to identify the extent of the Municipal Improvement, as per the Project's Servicing Agreement.
 - The drawings must be submitted in a single PDF document.
 - The highlighted plan must indicate the direction in which the photographs were taken.
- Photographs, uploaded to ePlan, showing the entire fence (numbered, labeled, and dated).

The consultant shall refer to the [Standard Operating Practice \(SOP\) - Fencing CCC Inspection for Photo Submissions](#) document for further information and clarification on Photo Submissions for Fencing.

NOTE: If the City discovers incorrect information or any misrepresentation in the report within 30 days of the report being submitted, the CCC will be rejected. The application will have to be re-submitted for inspection with corrections.

21.4. Eligibility For Photo Inspections

Photo inspections may be used for small lengths of fencing (**up to 40m**), such as those along walkways and flankages. Longer sections of fencing and larger sites are not eligible for photo inspections and an on-site inspection with a Landscape Development Inspector is required.

2024 **Landscape Inspector Guidelines**

When submitting photos of fencing inspections, continuous photos for the entire fencing should be provided to the City as one complete package, documenting the state of the fence at the time of inspection. A minimum of one photo per 5 panels (approximately every 15 meters) is recommended.

The photographs must show the following:

- Installation as per approved Engineering Drawings and any other supplementary details. Any deviations will require Redline Drawings.
- Height of the fence, using a measuring tape as reference.
- Entire length of the fence, ensuring no sections are missing.
- Height of the bottom gap, using a measuring tape as reference.

To ensure ease of reference and review, photographs must be taken in sequential order, with temporary markers as reference points placed on or near the fence. All photographs should be numbered sequentially, appropriately labelled, and dated.

If deficiencies are identified during the inspection, the Consultant must take a photograph of the deficiency followed by another photograph showing the corrected deficiency.

The fence must not be covered in debris, such as mud, dirt, or snow, to the degree that the Landscape Development Inspector cannot properly inspect the fence. The Landscape Development Inspector must be able to observe and measure the gap between the bottom of the fence and the existing grade.

21.5. On Site Fence Inspections

Based Cores Inspection that we will ensure as City Inspector:

- To have the approved engineering drawing to inspect the site.
- It is built to detail engineering drawings, specification and or manuFACTurer specification.
- The private developer fence is in the private property of the propriety line (PL) by the acceptable range.
- The wood fence is completely stained where applicable.(See Standards)
- The 50mm gap at the base of the fence (clearance from the ground) is there.
- The final grade is there if not ensured to have a grading stake provided to show the correct grade once the site will be complete.

2024 **Landscape Inspector Guidelines**

- Posts are straight.
- No wood filler will be approved.

When assessing the condition of a wood screen fence, the following guidelines must be adhered to before approval can be granted by a Landscape Development Inspector:

- **Vertical Posts:** Posts with severe cracking that is visible on more than one side must be replaced. If a post has significant cracks on only one side, it will be accepted, provided these cracks do not split the post completely in two. All cracks, regardless of their size, must be stained on the inside to maintain a uniform appearance. Vertical posts with minor cracks on the baseboard or board are also acceptable.
- **Structural Integrity:** Any vertical post exhibiting severe warping or twisting must be replaced. However, light warping or twisting of posts and rails is permissible as long as it does not exceed one quarter of the post's thickness and does not pose a long-term structural issue.
- **Materials:** No wood filler will be approved for repairing cracks or other damages. This ensures that the natural integrity and appearance of the wood are maintained.

By following these standards, the structural and aesthetic quality of wood screen fences can be ensured, promoting durability and safety.

Final Grading and Landscaping: The final grade landscaping may not be completed at the time of the fence inspection. This may make it difficult to determine the final gap between the bottom of the fence and the ground and concrete pilings may be visible. Survey stakes may be requested on City land to show the final grade.

When the surrounding landscape has achieved FAC and the fence is yet to be inspected, it is pertinent to leave a gap between the bottom of the fence and the existing grade of about 50 mm - 75 mm (as specified in the City's landscape drawing details).

2024 Landscape Inspector Guidelines



Wood Screen fencing must be stained prior to installation. All wood cuts are to be coated with two coats of approved wood preservatives. All posts are to be pressure treated.



All posts to be pressure treated



Post and Rail fencing require wood stain

2024 Landscape Inspector Guidelines



ESC sock needs to be removed and the landscape restored by the Developer.

ESC sock and silt fencing are located inside the private property and do not interfere with the city landscape.

21.6. Fencing FAC Inspection

Fencing improvements on City Property will require FAC. For general FAC processes and documentation submission requirements, please refer to [Section 18.0](#) of this document.

[\(back to top\)](#)

22. PLAYGROUND INSPECTIONS

Refer to:

- City's Design and Construction Standards, Volume 5: Landscaping, Section 9.3.
- ManuFACTurer's Manual, Servicing Agreement, and latest approved Engineering Drawings.
- [Playspaces and Wheeled Sport FACility Design and Construction Standards.](#)

22.1. Roles And Responsibilities

22.1.1. Landscape Development Inspector

- Review and approve pre-screen and department review submissions in ePlan.
- Assign IM Inspector for the Municipal Improvement in eServices.
- File CCC and FAC Inspection documents including the inspection report in the project Google Drive.

22.1.2. Infrastructure Maintenance (IM) Inspector

- Conduct pre-inspections, Hardstop Inspections, Audit Inspections, CCC and FAC Inspections for playground installations.
- Provide the Consultant with a written report following the completion of a Hardstop Inspection and CCC/FAC Inspections.
- Input the inspection results in eServices.

22.1.3. Transportation Development Inspector

- Conduct Hardstop Inspections related to subgrade, concrete sidewalks, curbs and playground skirts.

22.1.4. Developer/Consultant

- Invite all applicable stakeholders to a pre-construction meeting where the scope of work, schedule, project timelines, and communication plans are discussed.
- Contact the appropriate IM Inspector to arrange Hardstop Inspections and pre-inspection prior to conducting CCC Inspections.
- Upload required documents into ePlan prior to any scheduled inspection (see pre-inspection requirements).
- Upload required documents to ePlan after the approval of an inspection as part of the department review.

22.2. Playground Pre-Construction Meeting

Consultants/Developers are required to invite all relevant stakeholders for a kick-off or pre-construction meeting where the scope of work, schedule, project timelines, communication plans and any other relevant business are discussed.

Refer to [Appendix O: PLAYGROUND CCC/FAC CITY FORM](#)

22.3. Playground Construction Hardstop Inspection Requirements

There are stages in the playground construction process that are critical to ensure the safety and quality of the equipment. These critical inspection stages are referred to as hardstops that must be inspected before proceeding.

Hardstop Inspections must be conducted throughout the construction of the playground and tracked and recorded to be uploaded for the CCC Inspection application.

If a majority of the Hardstop Inspections are missed, the infrastructure installed will need to be removed and replaced at the discretion of the Inspectors (IM, Transportation, and/or other Subject Matter Experts).

22.3.1. Hardstop Inspections Application

To schedule a Hardstop Inspection, the Consultant must contact the appropriate inspector(s):

- Curtis Saulnier, Acting Infrastructure Maintenance Supervisor
(curtis.saulnier@edmonton.ca)
- [Transportation Development Inspector Group](#), contact the quadrant Inspector
- Subject Matter Expert - Landscape Development Supervisor, Olivier Le Tynevez-Dobel (olivier.letynevez-dobel@edmonton.ca)

The Infrastructure Maintenance, Transportation, or Subject Matter Expert inspector will document the required audits using a Playground Construction Hardstop Inspection Form, in which the Consultant must upload a completed form when applying for CCC.

22.3.2. Hardstop Inspection Stages

Hardstop Inspections must be requested between May 1st and November 30th, weather dependent (i.e. frozen ground, low temperatures, rain, snow, etc.) and may be canceled at the Landscape Development Supervisor's discretion.

Required Hardstop Inspection	Inspection Team
Base excavation and sub-base compaction for hard surFACes	Subject Matter Expert
Base excavation and sub-base compaction for playgrounds	Subject Matter Expert
Inspect the drainage pipe and weeping tile prior to the next step of the project	Subject Matter Expert
Inlet hook up and verification of grades with invert shots of weeping pipe drainage	Subject Matter Expert
Compaction of the sub-base of any hard surFACes and pour-in-place surFACes	Transportation Development Inspections
Testing as per the Landscape Development Inspector's request, ie. Head Impact Criteria (HIC) test	Infrastructure Maintenance Operations
Rebar in concrete slabs	Transportation Development Inspections

2024 Landscape Inspector Guidelines

Required Hardstop Inspection	Inspection Team
Curb pours	Transportation Development Inspections
Any concrete sidewalks / concrete skirts	Transportation Development Inspections
Equipment layout inspection - before pile foundation drilling	Infrastructure Maintenance Operations
Inspect and approve the auger holes with playground structure in place before concrete is poured, verify the size of the hole for footings (as per manuFACTurer) and plumb and level prior to pouring of footings	Infrastructure Maintenance Operations
Inspection of concrete pour for playground structures and any concrete clean-up needed on the play structures	Infrastructure Maintenance Operations
Inspect and approve the playground structures in place before safety surFACing is installed	Infrastructure Maintenance Operations
Final Inspection - post protective surFACing installation. Verify positive grading of the sub-base	Infrastructure Maintenance Operations
Inspection of the final surFACing and sub material as per drawing details	Infrastructure Maintenance Operations
Testing as per the Landscape Development Inspector's request, ie. HIC test	Infrastructure Maintenance Operations

22.4. Playground CCC Inspection Request Requirements

Prior to the CCC application, the Developer/Consultant must:

- Ensure the improvement is ready to be inspected (clean, accessible and unobstructed).
- The work must be concluded, and construction complete as per the approved Engineering Drawings.

2024 Landscape Inspector Guidelines

- Formally acknowledge that the improvement is complete, and is free of safety hazards. This will be confirmed by a “consultant pre-inspection report and (optional) checklist” supplied with the application for inspection. (See [Appendix G](#)).
- Arrange an Inspection with Infrastructure Maintenance after the installation of all equipment and protective surfACING prior to the CCC Inspection application.

22.5. Playground CCC Inspection Application

The inspection request must be initiated through eServices. An upload of supporting documents, to the Inspection Documents folder, on the specified ePlan Project is required to complete the request.

The upload to ePlan must include:

- CCC Landscape Inspection Request Form
- Consultant pre-inspection report and (optional) checklist (See [Appendix G](#))
- The latest City-approved Engineering Drawings (and/or Redline Drawings), updated with the changes made at CCC. **If any changes have occurred from the approved plans, upload updated plans. Failure to provide the updated plan for the inspection may result in an incomplete inspection.**
 - The drawings must be highlighted accordingly in order to identify the scope of inspection, matching the specified improvement within the Project's Servicing Agreement. (See [Appendix H](#))
- Playground Construction Hardstop Inspection Form, with noted and corrected deficiencies from the Hardstop Inspections conducted with the IM Inspector.
- Equipment installation manual
 - Submit compaction tests for subbase for review (compaction of subbase 98%, or as per plans, including under the playground curbing)
 - Concrete materials test (as per City's Design and Construction Standards)
 - Submit Head Impact Criteria (HIC) tests

22.6. Playground CCC Inspection

Once the document submission is in order, the Landscape Development Inspector will approve the pre-screen task on ePlan, assign the improvement to the IM Inspector in

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

eServices and the CCC Inspection will be coordinated by the IM Inspector with the Developer/Consultant.

At the time of CCC Inspection, the IM Inspector shall receive a maintenance kit from the Developer/Consultant:

- Maintenance kit (paint and hardware samples) to be provided to the City Playground Inspector at CCC Inspection. These items are requested to aid in the replacement of components or to complete minor repairs to the playground structure. These may include items such as paint samples, general bolts or rivets to verify size and style.

The IM Inspector will provide the Consultant with an inspection report.

If deficiencies exist after the CCC Inspection:

- The Consultant will have 14 days to repair deficiencies and request a re-inspection by contacting the IM Inspector.
- No new deficiencies will be added to the list during the re-inspection, unless the deficiencies occurred between the initial inspection and the re-inspection, create a safety issue, or are significant in nature.
- Only one re-inspection will be permitted during the inspection process. If the identified deficiencies from the inspection are not rectified at the re-inspection, the CCC Inspection will be rejected in eServices and the Consultant will have to re-apply and request for a new inspection.

If the Consultant needs additional time to amend the deficiencies prior to the deadline, the Consultant may request to extend the 14-day deadline. Extensions may be granted at the IM Inspector's discretion.

If the inspection fails, the IM Inspector will input 'Not Approved' for the Inspection Results in eServices and the Consultant will need to reapply for a new CCC Inspection once the deficiencies are corrected.

When no deficiencies are noted in the CCC Inspection, the IM Inspector will input 'Approved' for the Inspection Results in eServices. The date for which the CCC Inspection was approved will be the benchmark date that will initiate the Warranty Period.

2024 Landscape Inspector Guidelines

The Landscape Development Inspector will review and verify documents uploaded in ePlan for the CCC Department Review and file the documents in the project folder in Google Drive.

22.7. Playground Warranty Period

Refer to the Servicing Agreement for the length of the Warranty Period.

The IM Inspector will conduct audits of the playground installation after CCC is achieved. These Audit Inspections are intended to identify any safety concerns and defects in the hardware/structure.

22.8. Playground FAC Inspection

See [Section 18.0](#) for general FAC Inspection and document requirements. FAC is to be conducted by the IM Inspector.

After completing the inspection, the IM Inspector will provide the Consultant with an inspection report.

When no deficiencies are noted during the FAC Inspection, the IM Inspector will input 'Approved' for the Inspection Results in eServices.

See [_FAC documents required at department review](#). In addition, the Developer must submit a Letter of Warranty for the playground structure and any poured-in-place surFACe.

The Landscape Development Inspector will review and verify documents uploaded in ePlan for the FAC Department Review and file the documents in the project folder in Google Drive.

23. SHARED PARK SITE INSPECTIONS

******Program is on hold until further notice******

The Shared Park Development (SPD) Program is an agreed-upon partnership program between the City of Edmonton and the development industry where Developers design, construct and pay for a substantial cost of park development. These parks are developed to provide communities with amenities such as sports fields, landscaping, social gathering areas, playgrounds and much more. A clear understanding of all stakeholders' roles is imperative to ensure efficiencies in the program and the quality of these parks.

Shared Park Sites consist of multiple components and as such, coordination with different inspectors is required. Any hard surfACING component will be inspected by the City's Transportation Development Inspections Unit and will include CCC and FAC approvals. Landscape components in relation to shared park sites will be inspected by the Landscape Development Inspections Unit and will only require CCC approval. If there are any variances, the terms of the certification are defined in the Shared Parks Agreement.

23.1. Roles And Responsibilities

The following outlines the roles and responsibilities of the different stakeholders throughout the CCC Inspections and approval process for Shared Park Sites.

23.1.1. Developer/Consultant

The Developer/Consultant is responsible for overseeing the construction of the site. They will ensure that start-up meetings are set up prior to construction including all relevant stakeholders and inspection units. They will ensure that proper steps are taken in order to certify completion by way of a CCC. This includes the markup of site deficiencies and circulation of the marked-up plan to all relevant inspection parties.

23.1.2. City's Development Inspections Unit

The City's Development Inspections Unit is responsible for completing the inspections for Shared Park Sites projects. They will perform audits and major milestone inspections during construction and will be responsible for communicating with the Consultant and the Shared Park Development Group throughout the certification process (inspections, ePlan, eServices

2024 **Landscape Inspector Guidelines**

and deficiencies). The Development Inspections Unit will issue CCC and FAC approvals following conjunction with the Shared Park Development Group. Documentation supporting the certificate approvals would be collected and reviewed.

23.1.3. Shared Park Development Group

As the owner of the Shared Park Development Agreement, this group will act as the Project Manager throughout the lifecycle of the project. This includes concept development, design, construction and establishment of the site. If the scope of any part of the project, including inspections, is beyond the landscape construction standards, the Shared Park Development Group will be the ultimate decision-making entity. This group will provide the final approval of the project at CCC, with consultation of the City's Development Inspections Unit.

23.1.4. City Operations

City Operations will be involved in the concept development and design review stages of the Shared Park project. They will assume responsibility for the maintenance of the site, in accordance with the SPD agreement once CCC is achieved.

23.2. Shared Park CCC Application

Prior to the construction of a Shared Park, the Developer/Consultant must:

- Ensure Engineering Drawings are approved.
- Ensure the Development Permit application is approved.
- Ensure on-site pre-construction meetings are conducted.
 - Parties involved include the Developer/Consultant, Contractor, Development Inspection Unit, and Shared Park Development Group
 - The list of milestone audits and the Municipal Improvements from the SPD Agreement are to be reviewed by all parties
 - The project timelines, lines of communication and the inspection requirements and process should be reviewed during the pre-construction meeting.

23.3. Shared Park CCC Inspection Request Requirements

Shared Park inspections shall follow the procedures outlined in this guideline as follows:

- Milestone Audit Inspections shall be conducted by the City's Development Inspections Unit, as noted in Section 12.0 of this document, with notification to the SPD Group. Refer to the Shared Park Agreement for the list of required Milestone inspections. The [2024 Landscape Development Intake Requests Form](#) is available in the City's website and is to be submitted 48 hours prior to construction.
- Refer to Section 15.0 of this document for CCC Inspection procedures, with notification to the SPD Group of all inspections and Deficiency Plans.

23.4. Shared Park CCC Certificate Requirements

Since Shared Park projects are handed over to the City at CCC, all documentation is required to be provided at CCC application. New Shared Park projects are in ePlan and documentation is submitted through the normal department review processes. Any Shared Park projects not in ePlan will require submission of the document package with the paper application.

The submission of the documentation package for department review in ePlan must include the following:

- Signed Milestone Audit Inspection Form
- Maintenance Logs
- Separate Landscape Plan (PDF file format) indicating the year planted (single searchable PDF document) for all trees. Must be indicated on a copy of the as-built drawing (See [Appendix L](#))
- Asset Cost Form (ACF)
- As-Built Drawings
 - PDF
 - AutoCAD

23.5. Appeal Process

If there is a disagreement with the observations of the Landscape Development Inspector, the Developer/Consultant may request a review/appeal to the Landscape Development

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

Inspector. The Developer/Consultant shall identify areas of concern noted on the Deficiency Plan and present them to the SPD Group within 14 days.

If the scope is beyond the landscape construction standard, the Developer/Consultant will determine the reason and justification for the discrepancy and present it to the SPD Group. Depending on the deficiency presented, a site inspection may be required. The SPD Group will then make the decision to approve or reject the deficiencies, based on the reasoning provided. The SPD Group will need to document the justification of their decision and ensure that all affected stakeholders are contacted.

The SPD Group may approve the CCC and provide written notification to the Development Inspections Unit to complete the approval in eServices and the documentation approval tasks in ePlan.

24. NATURAL AREAS INSPECTIONS

24.1. Intent Of Inspection For Natural Sites

See [Appendix E](#) for the Natural Area Inspection Checklist.

References:

- Project's Servicing Agreement
- Site-Specific Natural Area Management Plan (SSNAMP)
- [City-Wide Natural Area Management Plan \(NAMP\)](#)
- City Policy - C531 Natural Area Systems supersedes City Policy - C467
- Corporate Tree Management Policy (C456C)
- Municipal Government Act (MGA)
- Migratory Birds Convention Act (Federal)
- Species at Risk Act (Federal)
- Fish and Wildlife Act (Provincial)
- Alberta Weed Control Act

24.2. Pre-Construction Inspection Of Natural Area

The Pre-Construction Inspection is required for documenting any disturbance to the natural area after the Engineering Drawings are approved and prior to construction, during the inspection season. This will identify safety concerns and any requirements still needing remediation, as per the Natural Area Management Plan (NAMP). Failure to contact Landscape Development Inspections may result in additional deficiencies at the time of CCC as the Landscape Development Inspector will be unable to determine or establish the condition of the site prior to the construction occurring. The Natural Area Inspection Checklist shall be completed by the Consultant to track the site conditions before, during and after construction, see [Appendix E](#) for the checklist.

To conduct the Pre-Construction Inspection, the following steps must be taken:

- The Consultant shall submit a request for inspection using the appropriate Google Form with a minimum of 48 hours notice prior to the start of construction activities.
- Submit plans highlighting the entirety of the natural area boundary. Submission should also include the SSNAMP if applicable.
- The site should be staked out, clearly indicating the boundaries of the improvement being inspected.
- Confirmation of the inspection appointment by the Landscape Development Inspector following coordination with all applicable inspectors and stakeholders.
- During the pre-construction inspection, items of concern are documented on the highlighted map provided.
- Photographs to document pre-construction conditions shall be taken. Refer to the [Checklist](#) requirements for more info.
- Documentation created for and during the pre-construction inspection will be saved in the project folder in Google Drive by the Landscape Development Inspector.

24.3. Audit Inspections

See [Section 12.0](#) of this document for general audit requirements.

The Landscape Development Inspector will monitor the site throughout the construction of the development area in order to ensure that no disturbance of the identified Natural Area(s) occur(s).

24.4. Natural Areas CCC / FAC Inspections

As per the Project's Servicing Agreement, some natural areas will not require FAC since no other improvements to the site will be added (left in the intended state).

The CCC and FAC Inspections are to follow the inspection processes outlined in [Section 15.0](#) and [Section 18.0](#) of this document, respectively. **In addition to these requirements, when applying for an inspection, Natural Areas shall have the following uploaded to ePlan for Pre-Screen approval, prior to inspection:**

- Pre-construction inspection report capturing site conditions prior to construction. Other supporting documents may include:
 - Supplementary documentation in adherence to the NAMP.
 - Site photos indicating pre-construction conditions.
- A pre-inspection report.

The Landscape Development Inspector shall inspect the Natural Area for the following inspection criteria outlined below:

- Disturbance: The Landscape Development Inspector shall look for evidence of disturbance in the Natural Area, including but not limited to:
 - Dumping and stockpiling or excavation
 - Change in grade
 - Noxious and prohibited noxious weeds, in accordance with the Alberta Weed Control Act
 - Identify any environmental issues and ensure appropriate corrective action or controls are in place
- Sensitive or protected features to be aware of:
 - Wildlife and wildlife habitat (consider both terrestrial and aquatic animals)
 - Evidence of birds nests or presence of birds
 - Water bodies (e.g., wetlands, streams, creeks)

2024 Landscape Inspector Guidelines

- Vegetation (e.g., trees, rare plants)
- Archeological, paleontological, and/or other historical resources
- Parks, protected and other designated lands
- Site contamination and/or other underground infrastructure (e.g., monitoring wells, and pipelines)
- Approved development in a Natural Area (ie. trails) should be a separate improvement item.
- If the Natural Area is affected by any construction related activities, restoration and/or remediation will be assigned to the Natural Area improvement.
- If tree removals are required as a result of a tree risk assessment in relation to the trails adjoining the Natural Area, that requirement will be assigned to the “top of bank” improvement.



Disturbance to Natural Areas

2024 Landscape Inspector Guidelines



Disturbance to Natural Areas



Natural Sites, Undisturbed

25. LOW IMPACT DEVELOPMENT (LID) INSPECTIONS

Refer to the City's Design and Construction Standards, Volume 3 and Volume 5, for information, along with other resources available in the City of Edmonton website:

[Low Impact Development \(LID\) | City of Edmonton](#)

APPENDIX A: CODE OF CONDUCT AND RESPECTFUL WORKPLACE

Return to the previous **Table of Contents** click [HERE](#)

Return to the previous Section 4 **Code of Conduct** click [HERE](#)

Refer to the City of Edmonton website for the current code of conduct:

[Code of Conduct | City of Edmonton](#)

[Respectful Workplace](#)

APPENDIX B: LANDSCAPE INSPECTIONS HAZARD ASSESSMENT

Return to the previous [Table of Contents](#) click [HERE](#)

Return to the previous Section [5.2 Field Level Hazard Assessment](#) click [HERE](#)

The following hazard assessment form is for Landscape Development Inspectors:

FORMAL HAZARD ASSESSMENT - JOB POSITION		Workforce Safety & Employee Health
Formal Hazard Assessment and Controls - Development Inspections Unit - Landscape - Landscape Technician II, ML2, GS.		
Date Created: January 16, 2024	Reviewed by: Olivier Le Tyneac-Dubé	Date of Last Revision:
Task: Development Inspection Landscaping Inspection in municipal environment	Designed By: Olivier Le Tyneac-Dubé	Revised By: Olivier Le Tyneac-Dubé
Position / Job code:		Approved By: Olivier Le Tyneac-Dubé
Landscape Reference #: ML2 - 4912, GS - 4137		Date of Last Revision:
The hazard assessment will be updated when a new work process has been introduced, introduction of new equipment, work processes have changed, lessons learned from an incident analysis and unhealthy working conditions have been noted.		
Personal Protective Equipment Required:		
1. Safety Footwear 2. Eye Protection 3. Appropriate Protective Clothing 5. High visibility vest 5. Hearing Protection (as required) 6. Hard hat 7. Other PPE as required		
Personal Protective Equipment "STANDARD" Required		
<ol style="list-style-type: none"> 1. SAFETY FOOTWEAR CSA Standard ISO 203 Protective Footwear (minimum 6" high) 2. SAFETY GLASSES must meet requirements outlined in: <ul style="list-style-type: none"> (i) CSA Standard Z94.3, 07, Eye and Face Protectors, (ii) CSA Standard Z94.3, 02, Eye and Face Protectors, or (iii) CSA Standard Z94.3, 99, Industrial Eye and Face Protectors 3. Appropriate Protective Clothing Long pants, shirt that covers over the shoulders, no, appropriate gloves, covers, PVC rain gear, sun glasses, sunscreen, insect repellent, bug spray, chemical resistant gloves and apron. 4. High Visibility Safety Apparel CSA Standard Z95-GS (Class 2 and 3 as minimum) 5. HEARING PROTECTION CSA Standard Z94.2-02 6. HARD HAT CSA Standard Z43.1-05, Industrial Protective headgear 7. Other: Cover UP, Disposable Face Mask, Heavy disposable gloves 		
General Training Required: Code of Conduct, Drug and alcohol, K9 in the City, OOD, Driving Permit, First Aid, Environmental Management System (Emsol), Soil Testing, Indigenous Awareness, Respectful Workplace Training, WHMIS, PACE Orientation Video, NBC Training, etc.		
Specific Task Training Required: Knowledge of Design and Construction Standards/Landscaping Volume 5, Landscaping Inspector Guideline, Urban Forest Management Plan		
Specific Task Safety Tasks: As required and "Jobcode Task: Cover UP Safety Apparel, Drive safely, Incident Reporting		
Management Responsibility: Continued Assessment and Evaluation of Programs, Complete Supervisor's Worstcase Inspectors, Knowledge of OHS Legislation (Regulation Act & Code), Knowledge of City Safety Directives and Procedures, Ensure Safety Policies, Programs, and Procedures are followed, Promote a Safe Work Environment.		

2024 Landscape Inspector Guidelines

2 City of Edmonton

Workforce Safety and Employee Health

Formal Hazard Assessment

Senior Landscape Technician III: Annual Update of Hazard Assessments & Controls (Annually by March 31). Complete Supervisor's Worksite Inspections. Ensure delivery of Safety Talk, knowledge of OH&S Legislation (Regulation, Act & Code.) Knowledge of City Safety Directives and Procedures. Ensure Safety Policies, Programs and Procedures are followed. Promote a Safe Work Environment.
 Landscape Technician II: Adhere to Hazard Assessments & Controls. Complete Worksite Inspections. Report any Safety Hazards. Follow Safe Working Procedures. Use Appropriate PPE. Put Safety First. Ask Questions if unsure. Private vehicle conditions: minimum Class 5 driver's license. Public Liability Business Insurance. (The employee responsible for all private vehicle maintenance.)

Assigned Value	Rating Matrix		
	1	2	3
Severity	First Aid	Lost Time Injury (Medical Aid or Temporary U/I)	Fatal (LTI Permanent Disability or Fatal)
Probability	Unlikely	Probable	Likely
Exposure	Rarely (less than once a month)	Often (three times a week)	Every Day
Rating Score	Serious 7, 8, 9 Moderate 5, 6 Low 3, 4	Note: Rate 1 is to be completed with no controls in place, and Rate 2 to be completed with controls in place	

The hazards listed on the forms are assessed according to the guidelines in the City of Edmonton Hazard Assessment and Control Standard. A summary of the terms used on the forms is given below			
S = Severity	If the hazard may result in a 1st Aid Incident, medical aid incident or minor property damage		Assign 1 point
	If the hazard may result in a lost time incident or significant property damage		Assign 2 points
	If the hazard may result in a permanent disability, fatality or major property damage		Assign 3 points
P = Probability	If an incident due to exposure to this hazard is unlikely to occur (i.e. possible but not probable)		Assign 1 point
	If an incident due to exposure to this hazard is likely to occur		Assign 2 points
	If an incident due to exposure to this hazard will occur		Assign 3 points

Updated January 16 2024

2024 Landscape Inspector Guidelines

3 City of Edmonton

Workforce Safety and Employee Health

Formal Hazard Assessment

E = Exposure	If the exposure to this hazard is rare (once per month or less)	Assign 1 point
	If the exposure to this hazard is often (more than once/month but less than 3 times per week)	Assign 2 points
	If the exposure to this hazard is routine (more than 3 times per week)	Assign 3 points
T = Total	Add points assigned from each category. Total is used to determine the level of risk that is associated with the identified hazard.	
	Total = 3 or 4	Low - L
	Total = 5 or 6	Moderate - M
Rating	Total = 7, 8 or 9	Serious - S
	Rate 1 - is without controls in place - Rate 2 - is with controls in place	
Definition of Rate		

Updated January 16 2024

2024 Landscape Inspector Guidelines

5 City of Edmonton

Workforce Safety and Employee Health

Formal Hazard Assessment

	2	3	4	5		1	1	3	4													
<p>Ergonomics Examples: Musculoskeletal injury and/or reduced productivity due to poor and incorrect workstation setup or design -Eye strain</p>						<ul style="list-style-type: none"> • Utilize the Remote Work Location Hazard Assessment & Inspection Form to assess Working from Home conditions. Review and confirm that all <u>Mandatory Safety Measures</u> are implemented in the Remote Location • Employees are aware of the Corporate Office Ergonomic Self-assessment Tool and City-Of-Ergonomic Supports. All concerns should be addressed to the supervisor and Corporate Ergonomist if needed <ul style="list-style-type: none"> ◦ Corporate purchasing standards should be in place to address the acquisition of new office furniture to ensure furniture is suitable for work tasks and ergonomically designed (Desks & Chairs) <ul style="list-style-type: none"> ◦ Use designated methods and expertise to set up and/or redesign workstation initially • Employee makes efforts to work in a neutral and supportive position with proper posture and maintains awareness while seated, i.e. (lower back supported and feet flat on floor or footrest) • Ensure monitor is at the proper height and distance level with the eyes, display screen clean and lighting is adequate, keyboard and mouse are within easy reach • Avoid extended phone use or utilizes headset to avoid deviated neck or shoulder positioning • Utilize safe manual lifting techniques • Take small breaks from tasks to stretch, move and change postures and take periodic rest breaks for eyes • Use appropriate equipment (i.e. Step Stool) to retrieve equipment and supplies from levels where reaching is required 																
<p>Manual Material Handling Examples: Awkward postures or over exertion due to oversized, awkward or heavy loads.</p>						<ul style="list-style-type: none"> • Assess and improve material handling conditions (e.g. weight of the object and the manner and frequency in which it is handled) • Awareness of proper body positioning • Staff should ask for assistance when required if the object is too heavy • Use equipment (dollies) to assist with manual material handling activities whenever practical • All staff are responsible to "Warm Up" and/or prepare themselves before handling the object • Staff should assess their readiness and capability for lifting the object before doing so 																

Updated January 16 2024

2024 Landscape Inspector Guidelines

6 City of Edmonton

Workplace Safety and Employee Health

Formal Hazard Assessment

		3	1	3	7	H		3	1	2	6	M
Walking to other sites for meetings from office	Severe weather conditions - cold, heat, snow, reduced visibility	1	1	2	4	L	<ul style="list-style-type: none"> Anticipate potential problems by listening to local weather forecasts Be familiar with the emergency procedures and prepared to respond appropriately if necessary Be prepared for the conditions by wearing hot or cold weather clothing, proper footwear, or rain gear If walking in the Downtown area, use indoor traffic routes (pedways) when possible 	1	1	1	3	L
Dealing with difficult colleagues or workload demands	Physiological Hazards: Stress in the workplace Overwork or burnout Fatigue or shift work Violence, Harassment, Bullying in the workplace	2	2	2	6	M	<ul style="list-style-type: none"> Employee Wellness and Supports page for emotional, physical, mental, and spiritual resources Employee and Family Assistance Program Lifeworks by Morneau Shepell 1-855-789-7289, 24/7 assistance Peer Support and City Chaplain John Dowds 780-496-7863 Mental Health First Aiders or Mental Health Living Consultants Safe disclosure office 1-844-296-6782 or safedisclosure.ca Utilizing the Disability Management team if needed The Working Mind training for employees and supervisors Respectful workplace training and directive for employees and supervisors 	2	1	1	4	L

Updated January 16, 2024

2024 Landscape Inspector Guidelines

7 City of Edmonton

Workforce Safety and Employee Health

Formal Hazard Assessment

Landscape Inspection Site Visits	Weather Elements - Sun Exposure (sun burns, dehydration, heat stroke), Lightning Exposure, Cold exposure, Air quality (Dust, Fines)	2	2	2	6	M	2	1	4	1	
						<ul style="list-style-type: none"> • Sunscreen • Keep Hydrated • Dress appropriately to the weather conditions • Take breaks when needed • Use shaded areas on sunny days to cool down • In extreme weather conditions, job may have to be rescheduled, consult with your supervisor • Pay attention to public health warnings and Reference Air quality index • Reduce levels of physical activity as necessary to decrease inhaling pollutants when air quality index is high • When air quality health index is high, utilize vehicle and keep windows closed, set ventilation to recirculate 					
	Severe weather conditions - cold, heat, snow, reduced visibility	1	1	2	4	L		1	1	3	
Working Alone Site Inspections (residential neighborhoods, schools, parks, river valley/ravines)		2	2	3	7	5	<ul style="list-style-type: none"> • Anticipate potential problems by listening to local weather forecasts • Be familiar with the emergency procedures and prepared to respond appropriately if necessary • Be prepared for the conditions by wearing hot or cold weather clothing, proper footwear (ie ice cleats, CSA rubber boots), or rain gear • Employee orientation, review working alone SOP v3 • Ensure to conduct FPHA prior to start inspection • Review location and establish site environment factors listed • Carry cell phones, inform Supervisor, colleagues and others of location prior to entry • Work in pairs if able to • Use check-in/out system after long periods with Supervisor • Wear required PPE. Ensure you are wearing CSA approved footwear and that your footwear is in good condition • Be prepared for the conditions by wearing hot or cold weather clothing, proper footwear (ie ice cleats, CSA rubber boots), or rain gear • On school sites - wear COE Identification - if children present leave site immediately - notify Supervisor - revisit in pairs • Be aware of footing (slopes, surface conditions) 	1	1	3	5

Updated January 16 2024

2024 Landscape Inspector Guidelines

City of Edmonton

Workforce Safety and Employee Health

Formal Hazard Assessment

					<ul style="list-style-type: none"> Be aware of your surroundings Ensure adequate lighting is in place Do not enter restricted or unsafe areas Ensure proper Safe Work Procedures are in place Establish safe distances from suspicious citizens or animals Contact RV Rangers for assistance if required when homeless camps or animals are present In extreme situations, job may have to be rescheduled, consult with your Supervisor 					
<p>Dealing with difficult members of the public or the vulnerable population Physiological Hazards Stress in the Workplace Violence and Harassment Verbal Abuse Domestic Violence Working in transient areas</p>		2	2	1	<ul style="list-style-type: none"> Conduct a thorough hazard assessment on-site and implement controls to minimize violent situations. Involve a supervisor if needed. Develop Emergency response plans if needed Be aware of your surroundings when dealing with difficult people, de-escalate if required, and remove yourself from the situation Report all incidents of violence in SOWS Education and training: De-escalation (dealing with difficult people training), Violence in the workplace training and prevention guide for staff that meets with external stakeholders or members of the public Corporate Administrative Directive and Procedures A1438 outline mitigation techniques Restricted building access (card-keys, locking/arming doors, etc.) Follow the City of Edmonton Working Alone Program requirements, i.e. employees and supervisors utilize check-in system Involve Corporate Security if needed 	1	2	1	4	L
<p>Working near/around mobile equipment, vehicles</p>		3	1	5	<ul style="list-style-type: none"> Avoid the working zone if possible Avoid positioning within a blind spot Avoid walking or working under a suspended load Maintain eye contact with the equipment operator Maintain awareness of surroundings at all times Hazard assessment and site orientation Watch the spotter on the ground for direction Ensure use of proper PPE including High-Viz Vest Avoid use of cell phone when working around mobile equipment 	2	1	1	4	L

Updated January 16 2024

2024 Landscape Inspector Guidelines

9 City of Edmonton

Workforce Safety and Employee Health

Formal Hazard Assessment

Noise	2	2	2	6	M	<ul style="list-style-type: none"> Leave site and return when all construction activity is shut down Hazard Assessment and Contractors identifying high noise area using signage (if possible) Wear hearing protection when exposed to noise over 85 dB and follow Occupational exposure limits 	1	1	1	3	L
Restricted and confined spaces	3	3	1	7	5	<ul style="list-style-type: none"> Do not enter confined spaces Do not enter restricted areas Ensure proper Safe Work procedures are in place 	1	1	1	3	L
Simultaneous operations	2	2	3	7	5	<ul style="list-style-type: none"> Communication and coordination with project managers and contractors Landscape Inspections guidelines, establishing their work site/zone access/egress areas 	1	2	1	4	L
Slip/trips/falls: Walking in adverse weather conditions, uneven ground, obstructions on ground, exposed or loose cables, wires or cords	2	2	2	6	M	<ul style="list-style-type: none"> Be aware of footing Ensure you are wearing CSA approved footwear and that your footwear is in good condition Ensure adequate lighting is in place Use designated walkways if possible General housekeeping, ensure pathways are free of trip hazards (Gravel paths, sand, ice melt) Utilize ice cleats when needed 	1	1	1	3	L
Working around Traffic	3	2	2	7	5	<ul style="list-style-type: none"> Use vehicle traffic advisory lighting when opening/parking COE vehicles. Field Level Hazard Assessment, pylons or cones, look in all directions - be aware of surroundings. OSCAM permit to detour traffic Wear required PPE (high-visibility vest) Work within barricades. Contractor is responsible for adequate traffic control layout (barricades, signage, reduced speed limits) Be aware of surroundings, include traffic zone in FLHA Avoid distracted walking and do your best to work facing oncoming traffic Trained flag person Whenever possible, stay away from traffic (ie. walk on the sidewalk vs on roadway) 	2	1	1	4	L

Updated January 16 2024

2024 Landscape Inspector Guidelines

10 City of Edmonton

Workforce Safety and Employee Health

Formal Hazard Assessment

Driving to Inspection Locations	Exposure to adverse weather conditions while driving	2 2 2 6	M	<ul style="list-style-type: none"> Plan ahead to use safer routes and to travel at safer times, utilize 511 for the most up to date province-wide road information Drive at reduced speeds and lengthen your following distance behind the vehicle 	1 2 2 5	M
	<p>Animal/Insect Exposure - Mosquitoes, Wasps, Bees, Fleas, Spiders, Dogs and Cats, Coyotes, Mice, Moose, Birds</p> <p>Air Quality Considerations During Landscape Inspection Site Visits.</p>	2 1 4	L	<ul style="list-style-type: none"> When backing up on site, use a spotter Contractors responsible for adequate lighting Ensure use of high vis-vest and other required PPE In extreme situations, job may have to be rescheduled, consult with your supervisor Insect Repellent Be aware of your surroundings, survey the area prior to work starting Maintain a safe distance from animals Hand protection Site orientation FLHA Mandatory Use of N95 Masks: Employees must wear N95 masks when the Air Quality Index (AQI) reaches levels that indicate unhealthy air conditions. Training on the correct usage, fitting, and disposal of N95 masks. Visibility and Eye Protection: Use of safety glasses or goggles to protect against eye irritation from smoke particles. Provision of high-visibility gear to ensure employee visibility in smoky conditions. Communication and Coordination: Establish a communication protocol for rapidly changing air quality conditions. Coordination with local health authorities for updates and guidelines. Health Monitoring: Regular health checks for employees working in smoky conditions. Immediate response plan for any respiratory distress or health issues. Work Scheduling and Breaks: Adjusting work schedules to avoid the smokiest periods. Providing more frequent breaks in a clean-air environment. 	1 1 3	L

Updated January 16 2024

2024 Landscape Inspector Guidelines

11 City of Edmonton

Workforce Safety and Employee Health

Formal Hazard Assessment

					<ul style="list-style-type: none"> • ahead of you. • Driving to the road conditions and driver capability • Ensure windshield if free of obstruction and that tires are in good condition • Following the City Driver Handbook and Distracted Driving Standard • if working alone, ensure you have a cellular phone to stay in contact with your supervisor • Do not drive if you are fatigued 			
Distracted driving and being Struck By or Striking other vehicles, pedestrians, objects	3	2	2	7	<ul style="list-style-type: none"> • Business insurance coverage for personal vehicles • Comply with the Distracted Driving Standard, City Driver Handbook, or City Policy regarding Car Rental At 415F if applicable • Ensure employees are aware of Drug and Alcohol policies • Before driving, walk around your vehicle to check that the path in front of and behind the vehicle is clear and that the blind zone is free of obstacles • Follow all rules of the road and comply with Alberta Traffic Safety Act • Wear your seat belt • Ensure windshield if free of obstruction and that tires are in good condition • Actively scan road and look for potential hazards that may develop ahead of you • Concentration on task, awareness of road conditions and other hazards • Obtain appropriate vehicle licenses and any stay informed about chemical hazards including WHMIS and TDG where applicable • Maintain safe distance behind vehicles ahead of you • Understand and Follow the City of Edmonton Distracted Driving Standard and the Traffic Safety Act • Avoid cell phone use, eating and multitasking while driving • Limit number of passengers and level of activity inside the car 	3	1	4
Mechanical Failure	2	1	1	4	<ul style="list-style-type: none"> • Complete a walk-around of your vehicle • Following City Driver Handbook • Regular Preventative Maintenance (PM) on City vehicles to ensure vehicle is in good working condition • Winterize vehicle when winter weather approaches • Carry an emergency kit in your vehicle • If working alone, ensure you have a cellular phone to stay in contact with your supervisor 	1	1	3
								L

Updated January 16 2024

2024 Landscape Inspector Guidelines

		Workforce Safety and Employee Health					Formal Hazard Assessment					
General Mental Health To prioritize and maintain the mental health and well-being of employees.	Slip/Trips/Falls From Vehicle	Z	2	2	6	M	<ul style="list-style-type: none"> Maintain 3 point contact when entering and exiting vehicles Be aware of footing, especially in icy conditions Situational awareness and hazard mitigation planning Use ice cleats if required 	1	1	2	4	L
	Stress and Burnout: Due to high workloads, tight deadlines, or challenging work environments.	Z	2	2	6	M	<ul style="list-style-type: none"> Stress Management Programs: Incentives like flexible work hours, wellness activities, and relaxation spaces in the workplace. Regular Mental Health Training: Educating employees on recognizing signs of mental distress in themselves and others. Training to include coping mechanisms and stress-reduction techniques. 	1	2	1	4	L
	Social Isolation: Especially in remote working scenarios.	Z	2	1	5	M	<ul style="list-style-type: none"> Communication Channel: Open lines for employees to discuss mental health concerns with supervisors or HR confidentially. Employee Assistance Programs (EAP): Access to professional counselling services and mental health resources. Peer Support Systems: Establishing a peer-led support group to provide a safe space for employees to share and discuss their concerns. Regular Check-ins: Management to conduct regular check-ins with employees to assess their mental state and offer support. Mental Health Days: Allowing employees to take days off specifically for mental health rest and recuperation. 	1	2	1	4	L
	Anxiety and Depression: Arising from work-related pressures or personal issues.	Z	2	2	6	M	<ul style="list-style-type: none"> Peer Support Systems: Establishing a peer-led support group to provide a safe space for employees to share and discuss their concerns. Regular Check-in: Management and HR to conduct regular check-ins with employees to assess their mental state and offer support. Work-Life Balance Policies: Implement policies that encourage a healthy balance between work and personal life, such as no-emails after work hours. Mental Health Days: Allowing employees to take days off specifically for mental health rest and recuperation. 	2	2	1	5	M

APPENDIX C: LANDSCAPE INSPECTION CHECKLIST

Return to the previous **Table of Contents** click [HERE](#)

Return to the previous Section **15 Construction Completion Certificate** click [HERE](#)

Return to the previous Section **16 Landscape Inspection Deficiencies** click [HERE](#)

LANDSCAPE CHECKLIST AT CCC

The following is a list of common items that must be inspected for a successful landscape inspection at CCC. This list is not exhaustive and other deficiencies may exist:

Trees (*Landscape Design and Construction Standards Specification No. 02930*)

- Trees are planted according to plan (location and species)
- Trees have acceptable vitality and form
- Correct size/caliper of specified plant material is installed.
- Tree planted as per city specification and approved drawing detail - the size of a tree well, flare, soil bump, amount of mulch, stakes and wires etc.
- Ensure wire baskets are cut or folded 1/3 down
- Trees are straight and aligned as necessary, especially along boulevards.
- Pests and diseases are not present or are controlled appropriately if applicable
- No wounds present
- Root form, no J root or girdling, no major root cuts
- Root flare is 40mm above grade
- Stakes are painted the correct colour by year planted.
- Dead, diseased and damaged plant material has been pruned and removed
- Suckers have been removed.
- All tree ties and flagging to be removed
- The Landscape Development Inspector can request tree protection and hoarding if located within 5m of active construction
- Ensure enough distance (2.5m) for mowers to pass through areas between individual trees and fences or other obstacles.
- Ensure the public boulevard is free of homeowner-installed items that are

[\(back to top\)](#)

2024 **Landscape Inspector Guidelines**

detrimental to the City trees such as landscape fabric or rock mulch. If these items are present at the time of audit or inspection, they should be pulled back from the base of the tree or removed entirely. It is the responsibility of the Developer/Consultant to contact the homeowner to educate them on how their private landscape items are impacting the City of Edmonton landscaping and how to avoid this from reoccurring in the future. However, if the Landscape Development Inspector deems that the homeowner's landscaping does not impede Operations, it can be left alone.

Shrubs / Perennials (*Landscape Design and Construction Standards Specification No. 02930*)

- Shrubs and perennials are planted according to plan (size, location and species)
- Topsoil and mulch are installed to the proper depth.
- Bed edges are cut in.
- Shrub spacing within beds is optimal for mature growth and a 0.5m offset from the edge of mature branch spreading (not of the new plant) to the edge of the bed, hardscape, fencing, gates, etc
- Plant material is healthy, has acceptable vitality, pest and disease free. If shrubs/perennials are not healthy and thriving in their current conditions, propose to add more instead of replacements, at the discretion of the Landscape Development Inspector and Consultant/Contractor.
- Ensure that if bollards or light standards are located near shrub beds, they are incorporated within the bed.
- Ensure enough distance (2.5m) for mowers to pass through areas between shrub beds and fences or other obstacles. If not enough distance, increase bed size to remove narrow turf areas.
- Ensure beds that taper along hard surFACes or fences allow mowers ease of maintenance with min. 45 degrees from fence lines etc.
- Ensure no mulch is installed on beds straddling, or below the 1:5 flood line of Stormwater Management FACilities (SWMFs).
- Pull soil/mulch away from the base of plant material.
- Are site conditions suitable for the proposed plant material? If not, an alternative species/design suggestion may be an option.
- For naturalized settings, ensure small shrubs and trees are visible/flagged for ease of inspection.

2024 Landscape Inspector Guidelines

Turf (*Landscape Design and Construction Standards Specification No. 02920*)

- Sod/seed is installed - Exception: Local boulevards are not required to have turf installed for CCC but must have, at a minimum, rough grade and no apparent safety hazards. Turf must be installed and established for FAC.
- Correct sod/seed mix is used.
- Are there any ruts? Ruts that pose a safety hazard must be repaired.
- Sod is even and flush with adjacent surFACes (manholes, vaults, mailboxes, walks, curbs, etc). Sod should never create an elevated lip above these surFACes as it will likely pose a drainage concern. Sod installed too low will cause a tripping hazard and is a safety concern.
- Weeds are being controlled - weeds show signs of die-back and no new weeds or seed-heads are present. Ensure the Contractor/Consultant are using all appropriate and required signage when spraying for weeds.
- Mow strip along the trail or fence line is present as per approved drawings
- Any low points or areas of uneven ground must be regraded to ensure proper drainage and to allow mowers to maintain.
- If sod won't grow, the Consultant can suggest alternative solutions with the approval of the Landscape Development Inspector.

General

- Everything is installed as per plans, in its correct quantity and location as per the approved design and details.
- Proper offsets are maintained from utilities, property lines, street furniture, etc.
- No safety concerns exist.
- Ensure there are no encroachments on city property (ie. homeowner landscaping). Contact Bylaw for encroachment issues (have Consultant contact 311).
- Soil requirements provided as per City of Edmonton Topsoil Specification.
- Homebuilder debris shall be removed.
- Is there remediation for damaged landscaping? This applies to sites within the same construction/development boundary and adjacent sites disturbed from the active construction of the improvement being inspected. This includes third party damage.
- Imminent hazards must be rectified prior to issuing certificate
- Aeration required in areas of soil compaction.

2024 Landscape Inspector Guidelines

- ❑ Erosion Control Measures have been installed and are functioning as designed as per approved drawings. Contact the EPCOR Drainage Inspector for erosion control issues.
- ❑ Debris, garbage, hazards, and run-off on site are removed.
- ❑ Any erosion cracking/washouts must be repaired.
- ❑ Ensure plant material is not blocking gates on chain link fence and they are able to fully open.
- ❑ Grading has positive drainage and does not pool (is there ponding or indication of too much moisture in locations – lack of plant health or indication of aquatic type plant material).
- ❑ Swales are not running through, or directed towards mulch beds.
- ❑ Side slopes that must be maintained by a mower are to have no more than a 3:1 slope.
- ❑ Boulders: Installation is permanent, safe and as per the detail/Standards
- ❑ Existing plant material: Trees that are existing on site, such as natural tree stands. This would be shown as per plan, have no safety hazards, and should have no construction disturbance. The plant material remains viable
- ❑ Other special features: As per plans for intended use (e.g. animal habitat)
- ❑ Low Impact Development (LID) features : Bioretention gardens & basins, soil cells and box planters installed as per plan
- ❑ Landscape Tie-In: This involves taking into account the natural features of the site, such as topography, existing vegetation, and waterways,so that the new landscaping project feels like it is part of the existing landscape. The goal of landscape tie-in is to create a harmonious relationship between the project in construction and the surrounding environment. (Transition to existing landscape)
- ❑ Lay down restoration: The goal of lay down area restoration is to restore the land to a natural and healthy state, while also ensuring that it is safe and stable for future use.

AUDITS DURING ESTABLISHMENT PERIOD

The following are general maintenance activities to be completed during the establishment period:

- Following maintenance plan
- Dead plant material replaced in a timely manner (2 weeks)
- Watering
- Fertilizing
- Mowing
- Weeds; controlled at CCC, eradicated for FAC.
- Pruning
- Pest control
- Garbage removal, as necessary

LANDSCAPE CHECKLIST AT FAC

The requirements listed above for CCC Inspections are also applicable deficiencies for FAC Inspections. The following is a list of additional specific items to inspect at FAC.

General

- Comments from CCC have been addressed ex. Redline Drawings were submitted, approved (if required), or approved Landscape In-Field Design Change
- Minor deficiencies have been corrected from CCC
- Everything on the most recently approved design plan is still present, alive, and exhibits good vitality and growth
- Erosion control may need to be added to protect the improvement from an adjacent site, or removed if no longer needed. Contact EPCOR Drainage Inspector if clarification or support is needed

Trees *(Landscape Design and Construction Standards Specification No. 02930)*

- Tree rejection criteria - the Landscape Development Inspector shall uphold the 10% Tree Rejection Allowance Rule for sites with 41+ trees and 25% tree rejection allowance for sites with 40 trees or less etc. See Section 4.8 (Warranty Period), or its equivalent, in the Design and Construction Standards (Volume 5: Landscaping) for additional information

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

- ❑ Trees that were installed after issuance of CCC and prior to FAC Inspection must be identified and will be inspected using CCC criteria.
- ❑ Trees from CCC are established and exhibit good vitality.
- ❑ The Landscape Development Inspector may request tree stakes to be removed if the tree is adequately established
- ❑ Tree wires are to be loosened prior to FAC Inspection to allow for further tree growth or are removed as necessary
- ❑ Trees have had structural pruning if necessary
- ❑ Mulch depth is installed as per detail

Shrubs / Perennials (*Landscape Design and Construction Standards Specification No. 02930*)

- ❑ Mulch is installed to the required depth.
- ❑ Weed control was successful during the Maintenance Period as per the Alberta Weed Control Act.
- ❑ Plant material is established, disease/pest free, and shows good vitality
- ❑ Quantities are correct from CCC Inspection.
- ❑ Flagging on small shrubs/trees is removed prior to approval, unless otherwise specified.
- ❑ Shrub rejection criteria - The Warranty Period will be extended to the following year for sites with more than 25 shrubs, where 25% or more of the total shrubs have not established and for sites with 25 shrubs or less, where 50% or more of the total shrubs have not been established.

Turf (*Landscape Design and Construction Standards Specification No. 02920*)

- ❑ Sod must be knit, and seed established.
- ❑ The Warranty Period will be extended to the following year for sites where more than 10% of the turf has not been established.
- ❑ Sod/Seeded area is able to withstand the stresses of the environment in which it is being grown
- ❑ Where naturalized seed is specified, sod is not a suitable alternative due to specific site conditions.
- ❑ Ruts and damage are repaired. Imminent hazards need to be repaired prior to issuing certificate.

[\(back to top\)](#)

2024 **Landscape Inspector Guidelines**

- ❑ Weeds are managed as per the Alberta Weed Control Act.
- ❑ SurFACe grading/tie-ins have not been changed or been damaged from CCC.
- ❑ Naturalized seed is not mowed below 150 mm height and is of the correct variety.
- ❑ If turf has too many damages from compaction, weeds etc., replace turf in all affected areas. Must be established at FAC application


APPENDIX D: CCC/FAC LANDSCAPE INSPECTION REQUEST FORMS

Return to the previous Section **Table of Contents** click [HERE](#)

Return to the previous Section **18.4 FAC Inspection Application** click [HERE](#)

Return to the previous Section **18.11.3 Phase 1: Initial CCC Submission** click [HERE](#)

2024 Landscape Inspector Guidelines



DEVELOPMENT INSPECTIONS - LANDSCAPE
 SUBDIVISION AND DEVELOPMENT COORDINATION
 CITY PLANNING
 URBAN FORM AND CORPORATE STRATEGIC DEVELOPMENT

CCC INSPECTION REQUEST FORM

SERVICING AGREEMENT

DEVELOPMENT NAME & STAGE:

MUNICIPAL IMPROVEMENT:

DESCRIPTION (AS LISTED IN ESERVICES):

EPLAN #:

DEVELOPER:

CONSULTANT:

CONTRACTOR:

REQUEST DATE:

SERVICING AGREEMENT NO.:

SIGNED SERVICING AGREEMENT DATE:

Total number of trees in municipal improvement: (If applicable) Does the site installation reflect the latest approved drawings/red-line? YES NO

CCC INSPECTION REQUEST CHECKLIST

	YES	NO	N/A
Inspection request submitted to eServices	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
Upload to ePlan the latest project drawings (and/or red-line) that have been approved by Development Coordination. Municipal improvement to be highlighted.	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
Upload pre-inspection report to ePlan	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
Upload maintenance schedule to ePlan (for landscape inspection requests)	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>


COMMENTS:

I hereby certify that the above mentioned improvement has been verified to meet all the necessary requirements for inspection. I understand that the request will be considered invalid if any of the above items are missing.

NAME OF APPLICANT: EMAIL:

CONTACT PHONE NO.:

2024 Landscape Inspector Guidelines



DEVELOPMENT INSPECTIONS - LANDSCAPE
 SUBDIVISION AND DEVELOPMENT COORDINATION
 CITY PLANNING
 URBAN FORM AND CORPORATE STRATEGIC DEVELOPMENT

FAC INSPECTION REQUEST FORM
 SERVICING AGREEMENT

DEVELOPMENT NAME & STAGE:

MUNICIPAL IMPROVEMENT:

REQUEST DATE:

DESCRIPTION (AS LISTED IN ESERVICES):

EPLAN #:

SERVICING AGREEMENT NO.:

SIGNED SERVICING AGREEMENT DATE:

END MAINTENANCE DATE:

DEVELOPER:

CONSULTANT:

CONTRACTOR:

Total number of trees in municipal improvement: (if applicable)

Does the site installation reflect the latest approved drawings/red-line?

YES

NO

FAC INSPECTION REQUEST CHECKLIST

	YES	NO	N/A
Inspection request submitted to eServices	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
Upload to ePlan the latest project drawings (and/or red-line) that have been approved by Development Coordination. Municipal improvement to be highlighted.	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
Upload pre-inspection report to ePlan	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>
Upload maintenance logs to ePlan (for landscape inspection requests)	<input type="radio"/>	<input type="radio"/>	<input type="radio"/>

COMMENTS:

I hereby certify that the above mentioned improvement has been verified to meet all the necessary requirements for inspection. I understand that the request will be considered invalid if any of the above items are missing.

NAME OF APPLICANT: EMAIL:

CONTACT PHONE NO.:

APPENDIX E: FENCING CCC INSPECTION PHOTO SUBMISSION


Return to the previous **Table of Contents** click [HERE](#)

Return to the previous Section **21.3. Application for Photo CCC Inspection** click [HERE](#)

The following are instructions for fencing applications via photo submission. This applies to small sections of fencing such as flankages and walkways. For larger fence improvements, an onsite inspection will be required.

2024 Landscape Inspector Guidelines

Standard Operating Practice (SOP) – Fencing CCC Inspections



Example of naming convention for photographs on ePlan

YYYY-MM-DD-TYPE OF FENCE & FENCE NUMBER-PHOTO NUMBER *(DEF (SPECIFIC DEFICIENCY), COR (DEFICIENCY CORRECTION), GEN (GENERAL DEFICIENCY))

- 2018-01-15-CL1-01
- 2018-01-15-CL1-01-GEN
- 2018-01-15-CL1-02
- 2018-01-15-CL1-03
- 2018-01-15-CL1-04 -DEF
- 2018-01-15-CL1-04 -DEF-COR
- 2018-01-15-CL1-04
- 2018-01-15-CL1-05
- 2018-01-15-CL1-06
- 2018-01-15-CL1-07
- 2018-01-15-CL1-08
- 2018-01-15-CL1-09
- 2018-01-15-WS1-01
- 2018-01-15-WS1-02
- 2018-01-15-WS1-03
- 2018-01-15-WS1-04

4

*if required

Standard Operating Practice (SOP) – Fencing CCC Inspections



Standard Operating Practice (SOP) – Fencing CCC Inspections



APPENDIX F: NATURAL AREA INSPECTION CHECKLIST

Return to the previous **Table of Contents** click [HERE](#)

Return to the previous Section **24.1 Intent of Inspections for Natural Sites** click [HERE](#)

Return to the previous Section **24.2 Pre-construction Inspection** click [HERE](#)

Natural Areas Site Inspection Report

Site Conditions Found	Recommended Amendments
Structures - previous landowner hazards	
Dumping - Garbage, debris or remaining potential hazards from previous Land Owner i.e. barbed wire, metals, equipment, fence posts etc.	
Noxious Weeds and/or Prohibited Noxious Weeds	
Site Disturbances - grade changes, stockpiling, compaction, evidence of staging, etc.	
Tree Concerns - Potential trees that present a moderate or high risk to targets i.e. Shared use paths or damage to private property.	
Tree pests or disease concerns	
Contamination or disturbance to water bodies (e.g., wetlands, streams, creeks, etc.)	
Site contamination and/or underground infrastructure that is active or not (e.g., monitoring wells, pipelines, spills etc..)	
Parks, provincial lands, protected and other designated lands	

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

Archeological, paleontological, and/or other historical resources	
Wildlife and wildlife habitats (terrestrial, avian, and aquatic animals, spawning) (check federal and provincial regulations)	
Vegetation (e.g., sensitive trees, rare plants, etc.) (check NAMP, SSNAMP or other resources)	
Encroachments	
Other deficiencies and safety concerns	

APPENDIX G: EXAMPLE OF A CONSULTANT PRE-INSPECTION REPORT & (OPTIONAL) CHECKLIST

Return to the previous **Table of Contents** click [HERE](#)

Return to the previous section **15.2 Preliminary CCC Inspection** click [HERE](#)

Return to the previous section **15.3 Consultant Requirements Prior to CCC Application** click [HERE](#)

Return to the previous section **15.4 Pre-Inspection Report** click [HERE](#)

Return to the previous section **18.2 Preliminary FAC Inspection** click [HERE](#)


Return to the previous section **18.3 Consultant Requirements Prior to FAC Application** click [HERE](#)

Return to the previous section **18.4 FAC Inspection Application** click [HERE](#)

Return to the previous section **18.11.3 Phase 1: Initial CCC Submission** click [HERE](#)

Return to the previous section **22.4 Playground CCC Inspection Request Requirements** click [HERE](#)

The Consultant's pre-inspection Report indicating the deficiencies to be corrected prior to inspection and date of pre-inspection is to be recorded. An example is seen below



CONSULTANT PRE-INSPECTION REPORT CHECKLIST (Optional)

Form can be accessed on the Landscape Inspector Guidelines Website, or [Here](#).

PRE-INSPECTION REPORT

Submissions required 30 days prior to the Eplan Inspection Request.

Location/Project Name:	Date:
Inspector:	Client/Contractor:

Landscaping Items Checklist		
Trees	Check if Applicable	Is the deficiency Corrected, if present?
Trees have acceptable vitality and form	<input type="checkbox"/>	<input type="checkbox"/>
Correct size/caliper of specified plant material installed	<input type="checkbox"/>	<input type="checkbox"/>
Tree planted as per city specification and approved drawing detail	<input type="checkbox"/>	<input type="checkbox"/>
Wire baskets are cut or folded 1/3 down	<input type="checkbox"/>	<input type="checkbox"/>
Trees are straight and aligned as necessary	<input type="checkbox"/>	<input type="checkbox"/>
Pests and diseases are controlled	<input type="checkbox"/>	<input type="checkbox"/>
Wound assessment	<input type="checkbox"/>	<input type="checkbox"/>

2024 Landscape Inspector Guidelines

PRE-INSPECTION REPORT

Submissions required 30 days prior to the Eplan Inspection Request.

Shrubs / Perennials	Check if Applicable	Is the deficiency Corrected, if present?
Planted according to plan (size, location, species)	<input type="checkbox"/>	<input type="checkbox"/>
Proper topsoil and mulch depth	<input type="checkbox"/>	<input type="checkbox"/>
Bed edges cut in	<input type="checkbox"/>	<input type="checkbox"/>
Optimal spacing for mature growth (0.5 m for mature spread from edge of pathways etc.)	<input type="checkbox"/>	<input type="checkbox"/>
Healthy, pest, and disease-free	<input type="checkbox"/>	<input type="checkbox"/>
Incorporate bollards or light standards within beds	<input type="checkbox"/>	<input type="checkbox"/>
Adequate space for mowers between beds and obstacles	<input type="checkbox"/>	<input type="checkbox"/>
Tapered beds for mower access	<input type="checkbox"/>	<input type="checkbox"/>
No mulch below SWMF flood line	<input type="checkbox"/>	<input type="checkbox"/>
Soil/mulch pulled away from plant base	<input type="checkbox"/>	<input type="checkbox"/>
Suitable site conditions for plant material	<input type="checkbox"/>	<input type="checkbox"/>
Visible/flagged small shrubs in naturalized settings	<input type="checkbox"/>	<input type="checkbox"/>
Seed, Sod or Turf Areas	Check if Applicable	Is the deficiency Corrected, if present?
Approved seed or sod mix	<input type="checkbox"/>	<input type="checkbox"/>
Appropriate establishment 90% established - no more than 10% not established & the 10% is not in concentrated areas	<input type="checkbox"/>	<input type="checkbox"/>
Repair ruts posing safety hazard	<input type="checkbox"/>	<input type="checkbox"/>
Weed control as per the Weed control Act of Alberta	<input type="checkbox"/>	<input type="checkbox"/>
If there are damaged areas of turf, appropriate amendments as necessary	<input type="checkbox"/>	<input type="checkbox"/>
Even sod flush with adjacent surfaces	<input type="checkbox"/>	<input type="checkbox"/>

[\(back to top\)](#)

2024 Landscape Inspector Guidelines

PRE-INSPECTION REPORT

Submissions required 30 days prior to the Eplan Inspection Request.

Mow strip along trail or fence line present	<input type="checkbox"/>	<input type="checkbox"/>
Repaired low points for proper drainage	<input type="checkbox"/>	<input type="checkbox"/>
Alternative solutions if sod, or seed won't grow	<input type="checkbox"/>	<input type="checkbox"/>
Aeration provided if there is evidence of compaction	<input type="checkbox"/>	<input type="checkbox"/>
If naturalized seed, mow no more than 1/3 of blade height or minimum height of 100-150mm	<input type="checkbox"/>	<input type="checkbox"/>
General	<u>Check if Applicable</u>	<u>Is the deficiency Corrected, if present?</u>
Installed per plans, quantity, and location	<input type="checkbox"/>	<input type="checkbox"/>
Proper offsets from utilities, property lines, etc.	<input type="checkbox"/>	<input type="checkbox"/>
No safety concerns	<input type="checkbox"/>	<input type="checkbox"/>
No encroachments on city property	<input type="checkbox"/>	<input type="checkbox"/>
Homebuilder debris removed	<input type="checkbox"/>	<input type="checkbox"/>
Remediation for damaged landscaping	<input type="checkbox"/>	<input type="checkbox"/>
Imminent hazards rectified	<input type="checkbox"/>	<input type="checkbox"/>
Aeration in areas of soil compaction	<input type="checkbox"/>	<input type="checkbox"/>
Erosion Control Measures as necessary	<input type="checkbox"/>	<input type="checkbox"/>
Debris, garbage, hazards removed	<input type="checkbox"/>	<input type="checkbox"/>
Repaired erosion cracking/washouts	<input type="checkbox"/>	<input type="checkbox"/>
Gates clear of plant material obstruction	<input type="checkbox"/>	<input type="checkbox"/>
Swales not directed towards mulch beds	<input type="checkbox"/>	<input type="checkbox"/>
Mower-friendly side slope maintenance	<input type="checkbox"/>	<input type="checkbox"/>
Permanent, safe boulder installations	<input type="checkbox"/>	<input type="checkbox"/>
Existing plant material remains viable	<input type="checkbox"/>	<input type="checkbox"/>

PRE-INSPECTION REPORT

Submissions required 30 days prior to the Eplan Inspection Request.

Special features installed per plans	<input type="checkbox"/>	<input type="checkbox"/>
LID features installed as per plan	<input type="checkbox"/>	<input type="checkbox"/>
Landscape Tie-In harmonious with surroundings	<input type="checkbox"/>	<input type="checkbox"/>
Lay down area restored to natural state	<input type="checkbox"/>	<input type="checkbox"/>
Grading	<u>Check if Applicable</u>	<u>Is the deficiency Corrected, if present?</u>
If the slopes are greater than 3:1, is the site naturalized?	<input type="checkbox"/>	<input type="checkbox"/>
Are there any low points causing ponding issues?	<input type="checkbox"/>	<input type="checkbox"/>
Is hardscape set at appropriate height to allow drainage as necessary	<input type="checkbox"/>	<input type="checkbox"/>
Is there erosion issues from adjacent property	<input type="checkbox"/>	<input type="checkbox"/>
Do you have the appropriate ESC measures in place to prevent damage to landscaping	<input type="checkbox"/>	<input type="checkbox"/>

APPENDIX H: EXAMPLE HIGHLIGHTED MAP FOR INSPECTION

Return to the previous **Table of Contents** click [HERE](#)

Return to the previous Section **15.4 The CCC Inspection Request** click [HERE](#)

Return to the previous Section **22.5 The CCC Playground Inspection Application** click [HERE](#)

Example A - Highlighted Inspection Report:

APPENDIX I: EXAMPLE OF TREE BUYOUT SUBMISSION

Return to the previous [Table of Contents](#) click [HERE](#)

Tree Buyout Declaration Form (a paper copy is to be included with the Buyout cheque):



DEVELOPER or REPRESENTATIVE TO COMPLETE THIS SECTION WHEN FINALIZING THE FAC TREE BUY OUT:

NEIGHBOURHOOD NAME & STAGE:

MUNICIPAL IMPROVEMENT NAME AND NUMBER: REQUEST DATE:

DEVELOPER:

CONSULTANT:

CONTRACTOR:

SERVICING AGREEMENT NO.: SIGNED SERVICING AGREEMENT DATE:

Final buy out Cost After Final Recheck

SUBTOTAL BUYOUT COST:

GST:

TOTAL BUYOUT COST (INCLUDING GST):

For Developer Use Only

DEVELOPER: DATE:

I hereby authorize the City of Edmonton to finalize the FAC Tree buy out. The cheque is in the amount shown in this form and will be submitted to the 2nd floor of the Edmonton Tower along with this document. All documentation will be provided to the City including As-Built drawings, TCA forms in order to complete the FAC process. I will maintain the landscape improvement until the buy out is completed and reimburse the City for any damages that may occur during the processing of the buy out.

Please submit cheque and this signed form to: 2nd Floor Edmonton Tower, 10111-104 Avenue NW, Edmonton, AB T5J 0J4, Payable to the City of Edmonton,

Cheque must be marked "Tree Buy Out+Servicing Agreement Number"

Attn. (DSA Engineer for this project)

For City of Edmonton Use Only

DEVELOPMENT INSPECTION SUPERVISOR:

APPROVED
 REJECTED

DATE:

2024 Landscape Inspector Guidelines

Tree Buyout Cost Estimate Excel Sheet Example:

TREE BUYOUT COST FORM 2024			
Project Name:		Neighbourhood and Stage	
Consultant Contact:		Name	
Date:			
Activity	Units	Unit Rate	Total Cost
Tree Planting			
2025 COE Decidious Replacement	3		\$ -
2025 COE Coniferous Replacement	1		\$ -
2025 COE Potted Replacement			\$ -
Watering			
1 year for establishment (2025 COE Replacement Plantings)	4		\$ -
1 year for establishment (2024 Developer Plantings)	2		\$ -
Extra year due to lack of vitality	1		\$ -
Tree Maintenance			
Slow Release Injection Fertilization			\$ -
Pruning (Structural)			
Trees up to 100mm cal and/or sucker removal			\$ -
Trees 110 - 250 mm cal			\$ -
Mature trees larger than 250mm cal			\$ -
Tree/Stump Removal			
Under 100mm cal	4		\$ -
110-250 mm cal			\$ -
Stump grinding			\$ -
Insect Treatment (List Issues)			
Sawfly	8		\$ -
Ground Work			

The Consultant fills out the sections outlined in red and Forestry will provide a cost estimate within 5 days of receiving the uploads of the Tree Buyout Submission.

APPENDIX K: EXAMPLE AS-BUILT PLANS


Return to the previous [Table of Contents](#) click [HERE](#)

Return to the previous Section [15.7.1 When FAC is not Required for the Municipal Improvement](#) click [HERE](#)

Return to the previous Section [18.8 FAC Documentation Requirements](#) click [HERE](#)


Return to the previous Section [18.9 Common Accuracy Items in As-Built Drawings](#) click [HERE](#)

Example A - As Built Plans:



KEY PLAN
SCALE: N.T.S.

PLANTING REQUIREMENTS FOR 6.0m WALKWAY:
 THE WALKWAY WILL RECEIVE PLANT MATERIAL AS FOLLOWS:
REQUIRED PLANTING: MIN. 4 TREES PER 35 METERS
 (MAY SUBSTITUTE 7 SHRUBS FOR 1 TREE
 UP TO A MAXIMUM OF 10%)
PROPOSED PLANTING: TOTAL LENGTH = 44m = 5 TREES
 0 UNITS OF 80mm CAL. TREES
 28 UNITS OF 1 GAL. (OR LARGER) POTTED SHRUBS
 * NO TREES DUE TO CONFLICTS WITH UTILITIES.



1 WALKWAY PLANTING PLAN
SCALE: 1:200

SOD MIX
 CERTIFIED CANADA NO. 1 CULTIVATED TURF, 80% WITH STRONG
 FIBROUS ROOT SYSTEM, 10% CANE AND 10% GROWN IN SHADOW
 24 HOURS FROM THE TIME OF CUTTING. SOD TO BE FREE OF STONES,
 BARK, PIN SPECIES AND BARK SEEDS TO BE 16-18mm MAX. CUT
 TO UNIFORM STRIPS, WIDTH AND THICKNESS, AND OF THE
 FOLLOWING SIX OR APPROVED EQUAL:
 100% HEAVY DUCK BLEGGRASS
 0-10% CRISPEHEAD RED FESCUE
 0-10% PERENNIAL RYEGRASS
 TOTAL AREA WALKWAY = 132 m²


PLANTING BED AREAS		
LABEL	AREA	MULCH TYPE
D	52 m ²	CONIFEROUS SHREDED BARK
E	12 m ²	CONIFEROUS SHREDED BARK

PLANT MATERIAL LIST: (THIS SHEET ONLY)

QTY./SYM.	BOTANICAL/COMMON NAME	SIZE	CONDITION
DECIDUOUS SHRUBS			
20	<i>Berberis thunbergii</i> 'Golden Nugget'	300 mm HT. 180 mm #2 CONTAINER	CONTAINER GROWN, 4 CANES OR MORE, 300mm HT. WITH MIN. ROOT SPREAD 200mm
10	<i>Golden Nugget</i> BARBERY		
10	<i>Berberis thunbergii</i> 'Rose Glow'	300 mm HT. 180 mm #2 CONTAINER	CONTAINER GROWN, 4 CANES OR MORE, 300mm HT. WITH MIN. ROOT SPREAD 200mm
10	<i>Rose Glow</i> BARBERY		
CONIFEROUS SHRUBS			
10	<i>Flora alba</i> 'Nidiformis'	300 mm SPR. #2 CONTAINER	CONTAINER GROWN, OR BALLED & BURLAPPED WITH A MIN. ROOT BALL DIA. OF 200mm WITH DEPTH NOT LESS THAN 70% OF DIA.
10	<i>Flora alba</i> 'Nidiformis'		
10	<i>Juniperus sibirica</i> 'Cedary Carpet'	300 mm SPR. #2 CONTAINER	CONTAINER GROWN, OR BALLED & BURLAPPED WITH A MIN. ROOT BALL DIA. OF 200mm WITH DEPTH NOT LESS THAN 70% OF DIA.
10	<i>Cedary Carpet</i> JUNIPER		

NOTE: ALL PLANT MATERIAL MUST CONFORM TO THE CITY OF EDMONTON DESIGN AND CONSTRUCTION STANDARDS.


PLANTING REQUIREMENTS FOR 6.0m WALKWAY:
 THE WALKWAY WILL RECEIVE PLANT MATERIAL AS FOLLOWS:
REQUIRED PLANTING: MIN. 4 TREES PER 35 METERS
 (MAY SUBSTITUTE 7 SHRUBS FOR 1 TREE
 UP TO A MAXIMUM OF 10%)
PROPOSED PLANTING: TOTAL LENGTH = 30m = 4 TREES
 0 UNITS OF 80mm CAL. TREES
 28 UNITS OF 1 GAL. (OR LARGER) POTTED SHRUBS
 * NO TREES DUE TO CONFLICTS WITH UTILITIES.



2 WALKWAY PLANTING PLAN
SCALE: 1:200

Clear and concise As-Built drawing indicating what improvement(s) is being added to city inventory.

Example B - As Built Plans:



Areas highlighted are areas within the specific improvement on the As-Built plans, with all of its pertinent information including planting list, details, area calculations etc.


APPENDIX L: EXAMPLE LANDSCAPE PLAN INDICATING YEARS PLANTED

Return to the previous **Table of Contents** click [HERE](#)

Return to the previous Section **18.8 FAC Documentation Requirements** click [HERE](#)

Return to the previous Section **23.4 Shared Park CCC Certificate Requirements** click [HERE](#)


Example A - Years Planted Plan:



Colour legend that corresponds to tree stake planting colour is preferred. Ensure that the labels are visible and are not covered up.

2024 Landscape Inspector Guidelines

Example B - Years Planted Plan:




This example uses the colour legend and clearly identifies the year planted, however translucency of the colour coding would be preferred for legibility.

APPENDIX M: SOIL SAMPLE MAP

Return to the previous [Table of Contents](#) click [HERE](#)

Return to the previous Section [11.1.2 Developer/Consultant](#) click [HERE](#)

Return to the previous Section [11.2 Soil Testing Procedure](#) click [HERE](#)



In this example, the basic/native soil Type 1 will be sampled in 2 distinctly different places and to the depth of 300 mm (refer to Table 1 in Section 02910 in the Standards). The ornamental shrub beds have Type 4 soil which is sampled at a higher rate, 3 samples will be taken at a depth of 450 mm.

APPENDIX N: WEBSITE LINKS AND REFERENCE DOCUMENTS

Return to the previous **Table of Contents** click [HERE](#)

Return to the previous Section **15.5 CCC Inspection** click [HERE](#)

Return to the previous Section **12.2 Major Milestones** click [HERE](#)

Return to the previous Section **18.4 FAC Inspection Application** click [HERE](#)

Return to the previous Section **18.5 FAC Inspection** click [HERE](#)

[Landscape Inspector Guidelines | City of Edmonton](#) (webpage Link)

APPENDIX O: PLAYGROUND CCC/FAC CITY FORM

Return to the previous [Table of Contents](#) click [HERE](#)

Return to the previous Section [22.2 Playground Pre-Construction Meeting](#) click [HERE](#)

Parks and Roads Services
 Infrastructure Maintenance
 Bridges Structures and Open Space Maintenance

City of Edmonton
 10517 – 95 Street NW
 Edmonton, AB T5H 2C2



INSERT Playground: Construction Completion & Final Acceptance Inspections (CCC/FAC)

CCC Inspection Date: _____ Project Contact: _____
 Inspector(s): _____

FAC Inspection Date: _____ Project Contact: _____
 Inspector(s): _____

Deficiencies Noted

The following observations were noted during the playground inspection. Results are in reference to the CAN/CSA Z614-20 Childrens’ Playspace Standards and the City of Edmonton Playspace and Wheeled Sport Facility Design and Construction Standards.

Link to picture folder (if applicable): _____

Deficient Item (link picture)	CSA Z614 / COE Clause	Class Hazard *	Suggested Correction	Target Completion:	Correction Date:
Example: Structure: Wood Structure as slivers	12.3.1.1 There shall be no accessible sharp points or sharp edges.	C	Remove or sand down slivers	July 20, 2022	July 18, 2020

Checklist	Status			Comments, design revisions or other results:
	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Unknown	
All assets installed as per as-built	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

2024 Landscape Inspector Guidelines

Drainage inspected	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Unknown	
Post holes inspected before and after concrete	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Unknown	
Loose fill surfacing is 12" deep	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Unknown	
Surfacing meets HIC drop testing	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Unknown	
Playground meets CAN/CSA Z614-20 Standards	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Unknown	
Playground meets Playspace and Wheeled Sports Facility Design and Construction Standards (Ver 03, date 2022-08-11)	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Unknown	
Playground equipment manual and maintenance kit received	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Unknown	

CCC Approval	Status		Date:
Construction completion approval once deficiencies are mitigated:	<input type="checkbox"/> Yes	<input type="checkbox"/> No	

FAC Approval	Status		Date:
Final Acceptance approval once deficiencies are mitigated:	<input type="checkbox"/> Yes	<input type="checkbox"/> No	

Additional Considerations

The following were not tested but should be considered in the evaluation:

Item	CSA Z614-20 Clause
Natural Materials: Wood	7.4.1 Natural logs, branches, or similar that are provided (with or without manufacturing or machining) shall

2024 Landscape Inspector Guidelines

	<p>be selected for durability as well as structural integrity as per the requirements of Clause 9. Note: Consideration of dimensional size, shape, and weight is acceptable criteria for the natural stability requirements of Clause 9.2.</p>
Ropes	<p>7.6 Ropes shall be selected on the basis of durability, strength, elasticity, weight, resistance to vandalism, potential to cause skin burns or abrasion, and requirements for maintenance. Ropes shall be resistant to ultraviolet degradation. If ropes are mounted permanently on support(s), the rope should be steel-cored or equivalently cut-resistant.</p>
Surfacing	<p>10.1 Energy absorbency of a surfacing material: The surfacing material in the protective surfacing zone shall have a gmax not exceeding 200 and an HIC not exceeding 1000 when tested for the defined fall height.</p>

Appendix

EQUIPMENT HAZARD CLASS*	CRITERIA
CLASS 'A'	Any condition which has the potential to be life threatening or can cause severe, permanent injury.
CLASS 'B'	Any condition which has the potential to cause serious but non-disabling injury.
CLASS 'C' (Equipment hazards and all construction-related deficiencies)	Any condition which can cause slight injury, or may not have caused injury but does not meet current standards.